



SAMPLE DATA

Report of Analysis

Client:	Portal Partners Tri-Venture	Date Collected:	01/25/25 11:33
Project:	Amtrak Sawtooth Bridges 2025	Date Received:	01/27/25
Client Sample ID:	B-110-SB01	SDG No.:	Q1194
Lab Sample ID:	Q1194-01	Matrix:	SOIL
		% Solid:	88.3

Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units(Dry Weight)	Prep Date	Date Ana.	Ana Met.
Hexavalent Chromium	0.089	U	1	0.089	0.45	mg/Kg	01/27/25 14:25	01/28/25 09:49	7196A
Trivalent Chromium	14.7		1	0.57	0.57	mg/Kg		01/29/25 12:15	6010D

Comments:

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

D = Dilution

Q = indicates LCS control criteria did not meet requirements

H = Sample Analysis Out Of Hold Time

J = Estimated Value

B = Analyte Found in Associated Method Blank

* = indicates the duplicate analysis is not within control limits.

E = Indicates the reported value is estimated because of the presence of interference.

OR = Over Range

N =Spiked sample recovery not within control limits

Report of Analysis

Client:	Portal Partners Tri-Venture	Date Collected:	01/25/25 13:58
Project:	Amtrak Sawtooth Bridges 2025	Date Received:	01/27/25
Client Sample ID:	B-110-SB02	SDG No.:	Q1194
Lab Sample ID:	Q1194-02	Matrix:	SOIL
		% Solid:	57

Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units(Dry Weight)	Prep Date	Date Ana.	Ana Met.
Hexavalent Chromium	0.14	U	1	0.14	0.68	mg/Kg	01/27/25 14:25	01/28/25 09:50	7196A
Trivalent Chromium	109		1	0.88	0.88	mg/Kg		01/29/25 12:19	6010D

Comments:

U = Not Detected
LOQ = Limit of Quantitation
MDL = Method Detection Limit
LOD = Limit of Detection
D = Dilution
Q = indicates LCS control criteria did not meet requirements
H = Sample Analysis Out Of Hold Time

J = Estimated Value
B = Analyte Found in Associated Method Blank
* = indicates the duplicate analysis is not within control limits.
E = Indicates the reported value is estimated because of the presence of interference.
OR = Over Range
N =Spiked sample recovery not within control limits

Report of Analysis

Client:	Portal Partners Tri-Venture	Date Collected:	01/25/25 11:52
Project:	Amtrak Sawtooth Bridges 2025	Date Received:	01/27/25
Client Sample ID:	B-113-SB01	SDG No.:	Q1194
Lab Sample ID:	Q1194-03	Matrix:	SOIL
		% Solid:	86.9

Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units(Dry Weight)	Prep Date	Date Ana.	Ana Met.
Hexavalent Chromium	0.089	U	1	0.089	0.45	mg/Kg	01/27/25 14:25	01/28/25 09:51	7196A
Trivalent Chromium	9.71		1	0.57	0.57	mg/Kg		01/29/25 12:23	6010D

Comments:

U = Not Detected
LOQ = Limit of Quantitation
MDL = Method Detection Limit
LOD = Limit of Detection
D = Dilution
Q = indicates LCS control criteria did not meet requirements
H = Sample Analysis Out Of Hold Time

J = Estimated Value
B = Analyte Found in Associated Method Blank
* = indicates the duplicate analysis is not within control limits.
E = Indicates the reported value is estimated because of the presence of interference.
OR = Over Range
N =Spiked sample recovery not within control limits

Report of Analysis

Client:	Portal Partners Tri-Venture	Date Collected:	01/25/25 14:44
Project:	Amtrak Sawtooth Bridges 2025	Date Received:	01/27/25
Client Sample ID:	B-113-SB02	SDG No.:	Q1194
Lab Sample ID:	Q1194-04	Matrix:	SOIL
		% Solid:	64.7

Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units(Dry Weight)	Prep Date	Date Ana.	Ana Met.
Hexavalent Chromium	0.12	U	1	0.12	0.60	mg/Kg	01/27/25 14:25	01/28/25 09:58	7196A
Trivalent Chromium	24.2		1	0.77	0.77	mg/Kg		01/30/25 18:03	6010D

Comments:

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

D = Dilution

Q = indicates LCS control criteria did not meet requirements

H = Sample Analysis Out Of Hold Time

J = Estimated Value

B = Analyte Found in Associated Method Blank

* = indicates the duplicate analysis is not within control limits.

E = Indicates the reported value is estimated because of the presence of interference.

OR = Over Range

N =Spiked sample recovery not within control limits

Report of Analysis

Client:	Portal Partners Tri-Venture	Date Collected:	01/25/25 00:00
Project:	Amtrak Sawtooth Bridges 2025	Date Received:	01/27/25
Client Sample ID:	EB	SDG No.:	Q1194
Lab Sample ID:	Q1194-08	Matrix:	WATER
		% Solid:	0

Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units	Prep Date	Date Ana.	Ana Met.
Dissolved Hexavalent Chromium	0.0030	U	1	0.0030	0.010	mg/L		01/27/25 16:01	7196A
trivalent Chromium	0.010	U	1	0.010	0.010	mg/L		01/28/25 13:22	6010D

Comments: _____

U = Not Detected
 LOQ = Limit of Quantitation
 MDL = Method Detection Limit
 LOD = Limit of Detection
 D = Dilution
 Q = indicates LCS control criteria did not meet requirements
 H = Sample Analysis Out Of Hold Time

J = Estimated Value
 B = Analyte Found in Associated Method Blank
 * = indicates the duplicate analysis is not within control limits.
 E = Indicates the reported value is estimated because of the presence of interference.
 OR = Over Range
 N =Spiked sample recovery not within control limits



QC RESULT SUMMARY

Initial and Continuing Calibration Verification

Client: Portal Partners Tri-Venture
Project: Amtrak Sawtooth Bridges 2025

SDG No.: Q1194
RunNo.: LB134432

Analyte	Units	Result	True Value	% Recovery	Acceptance Window (%R)	Analysis Date
Sample ID: ICV Hexavalent Chromium	mg/L	0.503	0.5	101	90-110	01/27/2025
Sample ID: CCV1 Hexavalent Chromium	mg/L	0.498	0.5	100	90-110	01/27/2025
Sample ID: CCV2 Hexavalent Chromium	mg/L	0.500	0.5	100	90-110	01/27/2025

Initial and Continuing Calibration Verification

Client: Portal Partners Tri-Venture

SDG No.: Q1194

Project: Amtrak Sawtooth Bridges 2025

RunNo.: LB134452

Analyte	Units	Result	True Value	% Recovery	Acceptance Window (%R)	Analysis Date
Sample ID: ICV Hexavalent Chromium	mg/L	0.502	0.5	100	90-110	01/28/2025
Sample ID: CCV1 Hexavalent Chromium	mg/L	0.498	0.5	100	90-110	01/28/2025
Sample ID: CCV2 Hexavalent Chromium	mg/L	0.501	0.5	100	90-110	01/28/2025
Sample ID: CCV3 Hexavalent Chromium	mg/L	0.502	0.5	100	90-110	01/28/2025

Initial and Continuing Calibration Blank Summary

Client: Portal Partners Tri-Venture

SDG No.: Q1194

Project: Amtrak Sawtooth Bridges 2025

RunNo.: LB134432

Analyte	Units	Result	Acceptance Limits	Conc Qual	MDL	RDL	Analysis Date
Sample ID: ICB Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0027	0.01	01/27/2025
Sample ID: CCB1 Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0027	0.01	01/27/2025
Sample ID: CCB2 Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0027	0.01	01/27/2025

Initial and Continuing Calibration Blank Summary

Client: Portal Partners Tri-Venture
Project: Amtrak Sawtooth Bridges 2025

SDG No.: Q1194
RunNo.: LB134452

Analyte	Units	Result	Acceptance Limits	Conc Qual	MDL	RDL	Analysis Date
Sample ID: ICB Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0027	0.01	01/28/2025
Sample ID: CCB1 Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0027	0.01	01/28/2025
Sample ID: CCB2 Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0027	0.01	01/28/2025
Sample ID: CCB3 Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0027	0.01	01/28/2025

Preparation Blank Summary

Client: Portal Partners Tri-Venture

SDG No.: Q1194

Project: Amtrak Sawtooth Bridges 2025

Analyte	Units	Result	Acceptance Limits	Conc Qual	MDL	RDL	Analysis Date
Sample ID: LB134432BL							
Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.003	0.01	01/27/2025
Sample ID: PB166262BL							
Hexavalent Chromium	mg/Kg	< 0.2000	0.2000	U	0.079	0.4	01/28/2025

Matrix Spike Summary

Client:	Portal Partners Tri-Venture	SDG No.:	Q1194
Project:	Amtrak Sawtooth Bridges 2025	Sample ID:	Q1194-03
Client ID:	B-113-SB01MS	Percent Solids for Spike Sample:	86.9

Analyte	Units	Acceptance Limit %R	Spiked Result	Conc. Qualifier	Sample Result	Conc. Qualifier	Spike Added	Dilution Factor	% Rec	Qual	Analysis Date
Hexavalent Chromium	mg/Kg	75-125	1440		0.089	U	1480	40	97		01/28/2025

Matrix Spike Summary

Client:	Portal Partners Tri-Venture	SDG No.:	Q1194
Project:	Amtrak Sawtooth Bridges 2025	Sample ID:	Q1194-03
Client ID:	B-113-SB01MS	Percent Solids for Spike Sample:	86.9

Analyte	Units	Acceptance Limit %R	Spiked Result	Conc. Qualifier	Sample Result	Conc. Qualifier	Spike Added	Dilution Factor	% Rec	Qual	Analysis Date
Hexavalent Chromium	mg/Kg	85-115	45.1		0.089	U	46.0	2	98		01/28/2025

Matrix Spike Summary

Client:	Portal Partners Tri-Venture	SDG No.:	Q1194
Project:	Amtrak Sawtooth Bridges 2025	Sample ID:	Q1194-03
Client ID:	B-113-SB01MS	Percent Solids for Spike Sample:	86.9

Analyte	Units	Acceptance Limit %R	Spiked Result	Conc. Qualifier	Sample Result	Conc. Qualifier	Spike Added	Dilution Factor	% Rec	Qual	Analysis Date
Hexavalent Chromium	mg/Kg	75-125	40.3		0.089	U	46.0	2	88		01/28/2025

Duplicate Sample Summary

Client: Portal Partners Tri-Venture Project: Amtrak Sawtooth Bridges 2025 Client ID: B-113-SB01DUP	SDG No.: Q1194 Sample ID: Q1194-03 Percent Solids for Spike Sample: 86.9
---	---

Analyte	Units	Acceptance Limit	Sample Result	Conc. Qualifier	Duplicate Result	Conc. Qualifier	Dilution Factor	RPD/ AD	Qual	Analysis Date
Hexavalent Chromium	mg/Kg	+/-20	0.089	U	0.090	U	1	0		01/28/2025

Laboratory Control Sample Summary

Client: Portal Partners Tri-Venture

SDG No.: Q1194

Project: Amtrak Sawtooth Bridges 2025

Run No.: LB134432

Analyte	Units	True Value	Result	Conc. Qualifier	% Recovery	Dilution Factor	Acceptance Limit %R	Analysis Date
Sample ID	LB134432BS							
Hexavalent Chromium	mg/L	0.5	0.50		100	1	90-111	01/27/2025

Laboratory Control Sample Summary

Client: Portal Partners Tri-Venture

SDG No.: Q1194

Project: Amtrak Sawtooth Bridges 2025

Run No.: LB134452

Analyte	Units	True Value	Result	Conc. Qualifier	% Recovery	Dilution Factor	Acceptance Limit %R	Analysis Date
Sample ID	PB166262BS							
Hexavalent Chromium	mg/Kg	20	20.0		100	1	84-110	01/28/2025

Instrument ID: SPECTROPHOTOMETER-1

Daily Analysis Runlog For Sequence/QC Batch ID # LB134432

Review By	rubina	Review On	1/27/2025 4:57:24 PM
Supervise By	Iwona	Supervise On	1/27/2025 4:57:48 PM
SubDirectory	LB134432	Test	Hexavalent Chromium
STD. NAME	STD REF.#		
ICAL Standard	N/A		
ICV Standard	N/A		
CCV Standard	N/A		
ICSA Standard	N/A		
CRI Standard	N/A		
LCS Standard	N/A		
Chk Standard	WP111653,WP111652,WP111650,WP111649,WP111659,WP110380,WP111657,WP111658,WP111651,WP111656,WI		

Sr#	SampleId	ClientID	QcType	Date	Comment	Operator	Status
1	CAL1	CAL1	CAL	01/27/25 15:45			OK
2	CAL2	CAL2	CAL	01/27/25 15:46			OK
3	CAL3	CAL3	CAL	01/27/25 15:47			OK
4	CAL4	CAL4	CAL	01/27/25 15:48			OK
5	CAL5	CAL5	CAL	01/27/25 15:49			OK
6	CAL6	CAL6	CAL	01/27/25 15:50			OK
7	CAL7	CAL7	CAL	01/27/25 15:51			OK
8	ICV	ICV	ICV	01/27/25 15:52			OK
9	ICB	ICB	ICB	01/27/25 15:53			OK
10	CCV1	CCV1	CCV	01/27/25 15:54			OK
11	CCB1	CCB1	CCB	01/27/25 15:55			OK
12	RL Check	RL Check	SAM	01/27/25 15:56			OK
13	LB134432BL	LB134432BL	MB	01/27/25 15:57			OK
14	LB134432BS	LB134432BS	LCS	01/27/25 15:58			OK
15	Q1168-07	LOD-MDL-WATER-01	SAM	01/27/25 15:59			OK
16	Q1168-08	LOQ-WATER-02-QT1	SAM	01/27/25 16:00			OK
17	Q1194-08	EB	SAM	01/27/25 16:01			OK
18	CCV2	CCV2	CCV	01/27/25 16:02			OK

Instrument ID: SPECTROPHOTOMETER-1

Daily Analysis Runlog For Sequence/QC Batch ID # LB134432

Review By	rubina	Review On	1/27/2025 4:57:24 PM
Supervise By	Iwona	Supervise On	1/27/2025 4:57:48 PM
SubDirectory	LB134432	Test	Hexavalent Chromium
STD. NAME	STD REF.#		
ICAL Standard	N/A		
ICV Standard	N/A		
CCV Standard	N/A		
ICSA Standard	N/A		
CRI Standard	N/A		
LCS Standard	N/A		
Chk Standard	WP111653,WP111652,WP111650,WP111649,WP111659,WP110380,WP111657,WP111658,WP111651,WP111656,WI		

19	CCB2	CCB2	CCB	01/27/25 16:03			OK
----	------	------	-----	----------------	--	--	----

Instrument ID: SPECTROPHOTOMETER-1

Daily Analysis Runlog For Sequence/QC Batch ID # LB134452

Review By	rubina	Review On	1/28/2025 12:03:31 PM
Supervise By	Iwona	Supervise On	1/28/2025 12:10:07 PM
SubDirectory	LB134452	Test	Hexavalent Chromium
STD. NAME	STD REF.#		
ICAL Standard	N/A		
ICV Standard	N/A		
CCV Standard	N/A		
ICSA Standard	N/A		
CRI Standard	N/A		
LCS Standard	N/A		
Chk Standard	WP111659,WP110380,WP110381,WP111657,WP111249,WP111658		

Sr#	SampleId	ClientID	QcType	Date	Comment	Operator	Status
1	CAL1	CAL1	CAL	01/28/25 09:30			OK
2	CAL2	CAL2	CAL	01/28/25 09:31			OK
3	CAL3	CAL3	CAL	01/28/25 09:32			OK
4	CAL4	CAL4	CAL	01/28/25 09:33			OK
5	CAL5	CAL5	CAL	01/28/25 09:34			OK
6	CAL6	CAL6	CAL	01/28/25 09:35			OK
7	CAL7	CAL7	CAL	01/28/25 09:36			OK
8	ICV	ICV	ICV	01/28/25 09:37			OK
9	ICB	ICB	ICB	01/28/25 09:38			OK
10	CCV1	CCV1	CCV	01/28/25 09:39			OK
11	CCB1	CCB1	CCB	01/28/25 09:40			OK
12	RL Check	RL Check	SAM	01/28/25 09:41			OK
13	PB166262BL	PB166262BL	MB	01/28/25 09:42			OK
14	PB166262BS	PB166262BS	LCS	01/28/25 09:43			OK
15	Q1168-01	LOD-MDL-SOIL-01-Q	SAM	01/28/25 09:44			OK
16	Q1168-02	LOQ-SOIL-02-QT1-20	SAM	01/28/25 09:45			OK
17	Q1169-01	ARS20-0006	SAM	01/28/25 09:46			OK
18	Q1169-03	REGULATOR-BUILD	SAM	01/28/25 09:47			OK

Instrument ID: SPECTROPHOTOMETER-1

Daily Analysis Runlog For Sequence/QC Batch ID # LB134452

Review By	rubina	Review On	1/28/2025 12:03:31 PM
Supervise By	Iwona	Supervise On	1/28/2025 12:10:07 PM
SubDirectory	LB134452	Test	Hexavalent Chromium
STD. NAME	STD REF.#		
ICAL Standard	N/A		
ICV Standard	N/A		
CCV Standard	N/A		
ICSA Standard	N/A		
CRI Standard	N/A		
LCS Standard	N/A		
Chk Standard	WP111659,WP110380,WP110381,WP111657,WP111249,WP111658		

19	Q1169-05	SPILL-SITE	SAM	01/28/25 09:48			OK
20	Q1194-01	B-110-SB01	SAM	01/28/25 09:49			OK
21	Q1194-02	B-110-SB02	SAM	01/28/25 09:50			OK
22	Q1194-03	B-113-SB01	SAM	01/28/25 09:51			OK
23	CCV2	CCV2	CCV	01/28/25 09:52			OK
24	CCB2	CCB2	CCB	01/28/25 09:53			OK
25	Q1194-03DUP	B-113-SB01DUP	DUP	01/28/25 09:54			OK
26	Q1194-03MSPre	B-113-SB01MS	MS	01/28/25 09:55			OK
27	Q1194-03MS2Ins	B-113-SB01MS	MS	01/28/25 09:56			OK
28	Q1194-03MS3Post	B-113-SB01MS	MS	01/28/25 09:57			OK
29	Q1194-04	B-113-SB02	SAM	01/28/25 09:58			OK
30	CCV3	CCV3	CCV	01/28/25 09:59			OK
31	CCB3	CCB3	CCB	01/28/25 10:00			OK

LAB CHRONICLE

OrderID:	Q1194	OrderDate:	1/27/2025 9:35:00 AM
Client:	Portal Partners Tri-Venture	Project:	Amtrak Sawtooth Bridges 2025
Contact:	Joseph Krupansky	Location:	N41,VOA Ref. #2 Soil,VOA Ref. #3 Water

LabID	ClientID	Matrix	Test	Method	Sample Date	Prep Date	Anal Date	Received
Q1194-01	B-110-SB01	SOIL			01/25/25 11:33	01/27/25	01/28/25 09:49	01/27/25
			Hexavalent Chromium	7196A				
			Trivalent Chromium	6010D			01/29/25 12:15	
Q1194-02	B-110-SB02	SOIL			01/25/25 13:58	01/27/25	01/28/25 09:50	01/27/25
			Hexavalent Chromium	7196A				
			Trivalent Chromium	6010D			01/29/25 12:19	
Q1194-03	B-113-SB01	SOIL			01/25/25 11:52	01/27/25	01/28/25 09:51	01/27/25
			Hexavalent Chromium	7196A				
			Trivalent Chromium	6010D			01/29/25 12:23	
Q1194-04	B-113-SB02	SOIL			01/25/25 14:44	01/27/25	01/28/25 09:58	01/27/25
			Hexavalent Chromium	7196A				
			Trivalent Chromium	6010D			01/30/25 18:03	
Q1194-08	EB	Water			01/25/25 12:00			01/27/25
			trivalent Chromium	6010D			01/28/25 13:22	

LAB CHRONICLE

Hexavalent Chromium	7196A	01/27/25 16:01
---------------------	-------	-------------------

A

C

D

E

F

SOP ID : M3060A,7196A-Hex.Chromium-26

SDG No : N/A

Matrix : SOIL

Pipette ID : WC

Balance ID : WC SC-7

Hood ID : HOOD#3

Block ID : WC S-2, WC S-1

Welgh By : RM

Start Digest Date: 01/27/2025 **Time :** 14:25 **Temp :** 90 °C

End Digest Date: 01/27/2025 **Time :** 15:25 **Temp :** 95 °C

if batch

01/27/2025

01/27/2025

15:40

16:40

90°C
95°C

Digestion tube ID : M6054

Filter paper ID : 400213

pH Meter ID : WC pH meter-1

Block Thermometer ID : WC-Block#1

Prep Technician Signature:

Supervisor Signature:

RM

12

Standard Name	MLS USED	STD REF. # FROM LOG
PRE-DIGESTION SPIKE	2.0ML	WP111315
INSOLUBLE SPIKE	0.02GM	W2202
POST-DIGESTION SPIKE	2.0ML	WP111315
LCSS	1.0ML	WP111316
PBS003	50.0ML	W3112

Chemical Used	ML/SAMPLE USED	Lot Number
MAGNESIUM CHLORIDE	0.4GM	W3152
PHOSPHATE BUFFER	0.5ML	WP110498
HEX. DIGESTION SOLN.	50.0ML	WP111384
5M HNO3	5-7ML	WP110381
5N H2SO4	1-3ML	WP110380
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A

LAB SAMPLE ID	CLIENT SAMPLE ID	Vol(ml)	Comment
CAL1	CAL1	2.5ML	W3112
CAL2	CAL2	0.2ML	WP111648
CAL3	CAL3	0.5ML	WP111648
CAL4	CAL4	1ML	WP111648
CAL5	CAL5	0.2ML	WP111315
CAL6	CAL6	1ML	WP111315
CAL7	CAL7	2.0ML	WP111315
ICV	ICV	1ML	WP111316
ICB	ICB	2.5ML	W3112
CCV	CCV	1ML	WP111315
CCB	CCB	2.5ML	W3112

Extraction Conformance/Non-Conformance Comments:

LOD WP111657, LOQ WP111658

01/27/2025 RM

Date / Time	Prepped Sample Relinquished By/Location	Received By/Location
	Preparation Group	Analysis Group

Lab Sample ID	Client Sample ID	Initial Weight (g)	Final Vol (ml)	pH	Sulfide	Oxidizing	Nitrate/Nitrite	Comment	Prep Pos
PB166262BL	PBS262	2.50	100	N/A	N/A	N/A	N/A	N/A	N/A
PB166262BS	LCS262	2.50	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1168-01	LOD-MDL-SOIL-01-QT1-2025	2.50	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1168-02	LOQ-SOIL-02-QT1-2025	2.50	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1169-01	ARS20-0006	2.57	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1169-03	REGULATOR-BUILDING-GRAVEL	2.54	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1169-05	SPIILL-SITE	2.52	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1194-01	B-110-SB01	2.52	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1194-02	B-110-SB02	2.57	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1194-03	B-113-SB01	2.54	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1194-03DUP	B-113-SB01DUP	2.53	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1194-03MSPre	B-113-SB01MSPRE	2.54	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1194-03MS2Ins	B-113-SB01MS2INS	2.54	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1194-03MS3Post	B-113-SB01MS3POST	2.56	100	N/A	N/A	N/A	N/A	N/A	N/A
Q1194-04	B-113-SB02	2.56	100	N/A	N/A	N/A	N/A	N/A	N/A