284 Sheffield Street, Mountainside, New Jersey 07092, Phone : 908 789 8900,
Fax : 908 789 8922

Report of Analysis

Client:	Sciacca General Contractors, LLC	Date Collected:	
Project:	32 Sayer Pl, Hillsdale	Date Received:	
Client Sample ID:	VY0516SBL01	SDG No.:	Q2003
Lab Sample ID:	VY0516SBL01	Matrix:	SOIL
Analytical Method:	8260D	% Solid:	100
Sample Wt/Vol:	5 Units: g	Final Vol:	5000 uL
Soil Aliquot Vol:	uL	Test:	VOC-TCLVOA-10
GC Column:	RXI-624 ID : 0.25	Level :	LOW
Prep Method :			

File ID/Qc Batch:	Dilution:	Prep Date	Date Analyzed	Prep Batch ID
VY022278.D	1		05/16/25 09:37	VY051625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
TARGETS						
75-71-8	Dichlorodifluoromethane	1.10	U	1.10	5.00	ug/Kg
74-87-3	Chloromethane	1.10	U	1.10	5.00	ug/Kg
75-01-4	Vinyl Chloride	0.79	U	0.79	5.00	ug/Kg
74-83-9	Bromomethane	1.10	U	1.10	5.00	ug/Kg
75-00-3	Chloroethane	1.30	U	1.30	5.00	ug/Kg
75-69-4	Trichlorofluoromethane	1.20	U	1.20	5.00	ug/Kg
76-13-1	1,1,2-Trichlorotrifluoroethane	1.10	U	1.10	5.00	ug/Kg
75-35-4	1,1-Dichloroethene	1.00	U	1.00	5.00	ug/Kg
67-64-1	Acetone	4.70	U	4.70	25.0	ug/Kg
75-15-0	Carbon Disulfide	1.10	U	1.10	5.00	ug/Kg
1634-04-4	Methyl tert-butyl Ether	0.73	U	0.73	5.00	ug/Kg
79-20-9	Methyl Acetate	1.50	U	1.50	5.00	ug/Kg
75-09-2	Methylene Chloride	3.50	U	3.50	10.0	ug/Kg
156-60-5	trans-1,2-Dichloroethene	0.86	U	0.86	5.00	ug/Kg
75-34-3	1,1-Dichloroethane	0.80	U	0.80	5.00	ug/Kg
110-82-7	Cyclohexane	0.79	U	0.79	5.00	ug/Kg
78-93-3	2-Butanone	6.50	U	6.50	25.0	ug/Kg
56-23-5	Carbon Tetrachloride	0.97	U	0.97	5.00	ug/Kg
156-59-2	cis-1,2-Dichloroethene	0.75	U	0.75	5.00	ug/Kg
74-97-5	Bromochloromethane	1.20	U	1.20	5.00	ug/Kg
67-66-3	Chloroform	0.84	U	0.84	5.00	ug/Kg
71-55-6	1,1,1-Trichloroethane	0.93	U	0.93	5.00	ug/Kg
108-87-2	Methylcyclohexane	0.91	U	0.91	5.00	ug/Kg
71-43-2	Benzene	0.79	U	0.79	5.00	ug/Kg
107-06-2	1,2-Dichloroethane	0.79	U	0.79	5.00	ug/Kg
79-01-6	Trichloroethene	0.81	U	0.81	5.00	ug/Kg
78-87-5	1,2-Dichloropropane	0.91	U	0.91	5.00	ug/Kg
75-27-4	Bromodichloromethane	0.78	U	0.78	5.00	ug/Kg
108-10-1	4-Methyl-2-Pentanone	3.60	U	3.60	25.0	ug/Kg
108-88-3	Toluene	0.78	U	0.78	5.00	ug/Kg

Alliance TECHNICAL GROUP
284 Sheffield Street, Mountainside, New Jersey 07092, Phone : 908 789 8900,
Fax : 908 789 8922

Report of Analysis

Client:	Sciacca General Contractors, LLC	Date Collected:	
Project:	32 Sayer Pl, Hillsdale	Date Received:	
Client Sample ID:	VY0516SBL01	SDG No.:	Q2003
Lab Sample ID:	VY0516SBL01	Matrix:	SOIL
Analytical Method:	8260D	% Solid:	100
Sample Wt/Vol:	5 Units: g	Final Vol:	5000 uL
Soil Aliquot Vol:	uL	Test:	VOC-TCLVOA-10
GC Column:	RXI-624 ID : 0.25	Level :	LOW
Prep Method :			

File ID/Qc Batch:	Dilution:	Prep Date	Date Analyzed	Prep Batch ID
VY022278.D	1		05/16/25 09:37	VY051625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
10061-02-6	t-1,3-Dichloropropene	0.65	U	0.65	5.00	ug/Kg
10061-01-5	cis-1,3-Dichloropropene	0.62	U	0.62	5.00	ug/Kg
79-00-5	1,1,2-Trichloroethane	0.92	U	0.92	5.00	ug/Kg
591-78-6	2-Hexanone	3.70	U	3.70	25.0	ug/Kg
124-48-1	Dibromochloromethane	0.87	U	0.87	5.00	ug/Kg
106-93-4	1,2-Dibromoethane	0.88	U	0.88	5.00	ug/Kg
127-18-4	Tetrachloroethene	1.10	U	1.10	5.00	ug/Kg
108-90-7	Chlorobenzene	0.91	U	0.91	5.00	ug/Kg
100-41-4	Ethyl Benzene	0.67	U	0.67	5.00	ug/Kg
179601-23-1	m/p-Xylenes	1.20	U	1.20	10.0	ug/Kg
95-47-6	o-Xylene	0.82	U	0.82	5.00	ug/Kg
100-42-5	Styrene	0.71	U	0.71	5.00	ug/Kg
75-25-2	Bromoform	0.86	U	0.86	5.00	ug/Kg
98-82-8	Isopropylbenzene	0.78	U	0.78	5.00	ug/Kg
79-34-5	1,1,2,2-Tetrachloroethane	1.20	U	1.20	5.00	ug/Kg
541-73-1	1,3-Dichlorobenzene	1.70	U	1.70	5.00	ug/Kg
106-46-7	1,4-Dichlorobenzene	1.60	U	1.60	5.00	ug/Kg
95-50-1	1,2-Dichlorobenzene	1.50	U	1.50	5.00	ug/Kg
96-12-8	1,2-Dibromo-3-Chloropropane	1.80	U	1.80	5.00	ug/Kg
120-82-1	1,2,4-Trichlorobenzene	3.00	U	3.00	5.00	ug/Kg
87-61-6	1,2,3-Trichlorobenzene	3.20	U	3.20	5.00	ug/Kg
SURROGATES						
17060-07-0	1,2-Dichloroethane-d4	43.9		70 (63) - 130 (155)	88%	SPK: 50
1868-53-7	Dibromofluoromethane	47.9		70 (70) - 130 (134)	96%	SPK: 50
2037-26-5	Toluene-d8	48.8		70 (74) - 130 (123)	98%	SPK: 50
460-00-4	4-Bromofluorobenzene	48.5		70 (38) - 130 (136)	97%	SPK: 50
INTERNAL STANDARDS						
363-72-4	Pentafluorobenzene	314000	7.707			
540-36-3	1,4-Difluorobenzene	556000	8.616			
3114-55-4	Chlorobenzene-d5	426000	11.42			
3855-82-1	1,4-Dichlorobenzene-d4	151000	13.347			

284 Sheffield Street, Mountainside, New Jersey 07092, Phone : 908 789 8900,
Fax : 908 789 8922

Report of Analysis

Client:	Sciacca General Contractors, LLC	Date Collected:	
Project:	32 Sayer Pl, Hillsdale	Date Received:	
Client Sample ID:	VY0516SBL01	SDG No.:	Q2003
Lab Sample ID:	VY0516SBL01	Matrix:	SOIL
Analytical Method:	8260D	% Solid:	100
Sample Wt/Vol:	5 Units: g	Final Vol:	5000 uL
Soil Aliquot Vol:	uL	Test:	VOC-TCLVOA-10
GC Column:	RXI-624 ID : 0.25	Level :	LOW
Prep Method :			

File ID/Qc Batch:	Dilution:	Prep Date	Date Analyzed	Prep Batch ID
VY022278.D	1		05/16/25 09:37	VY051625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units

U = Not Detected
LOQ = Limit of Quantitation
MDL = Method Detection Limit
LOD = Limit of Detection
E = Value Exceeds Calibration Range
Q = indicates LCS control criteria did not meet requirements
M = MS/MSD acceptance criteria did not meet requirements

J = Estimated Value
B = Analyte Found in Associated Method Blank
N = Presumptive Evidence of a Compound
* = Values outside of QC limits
D = Dilution
() = Laboratory InHouse Limit
A = Aldol-Condensation Reaction Products