

Report of Analysis

Client:	Union Paving & Construction Company		Date Collected:	06/23/25	
Project:	190 Park Ave Hanover Twp NJ - PO 2556-001		Date Received:	06/23/25	
Client Sample ID:	PARK AVE -3		SDG No.:	Q2393	
Lab Sample ID:	Q2393-05		Matrix:	SOIL	
Analytical Method:	8082A		% Solid:	86.6	Decanted:
Sample Wt/Vol:	30.06	Units: g	Final Vol:	10000	uL
Soil Aliquot Vol:		uL	Test:	PCB	
Extraction Type:			Injection Volume :		
GPC Factor :	1.0	PH :			
Prep Method :	SW3541B				

File ID/Qc Batch:	Dilution:	Prep Date	Date Analyzed	Prep Batch ID
PP073243.D	1	06/25/25 08:45	06/25/25 14:53	PB168607

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
TARGETS						
12674-11-2	Aroclor-1016	4.60	U	4.60	19.6	ug/kg
11104-28-2	Aroclor-1221	4.60	U	4.60	19.6	ug/kg
11141-16-5	Aroclor-1232	4.30	U	4.30	19.6	ug/kg
53469-21-9	Aroclor-1242	4.60	U	4.60	19.6	ug/kg
12672-29-6	Aroclor-1248	6.80	U	6.80	19.6	ug/kg
11097-69-1	Aroclor-1254	3.70	U	3.70	19.6	ug/kg
37324-23-5	Aroclor-1262	5.80	U	5.80	19.6	ug/kg
11100-14-4	Aroclor-1268	4.10	U	4.10	19.6	ug/kg
11096-82-5	Aroclor-1260	3.70	U	3.70	19.6	ug/kg
SURROGATES						
877-09-8	Tetrachloro-m-xylene	17.5		32 - 144	88%	SPK: 20
2051-24-3	Decachlorobiphenyl	17.4		32 - 175	87%	SPK: 20

Comments:

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

E = Value Exceeds Calibration Range

P = Indicates >25% difference for detected concentrations between the two GC columns

Q = indicates LCS control criteria did not meet requirements

M = MS/MSD acceptance criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

N = Presumptive Evidence of a Compound

* = Values outside of QC limits

D = Dilution

S = Indicates estimated value where valid five-point calibration was not performed prior to analyte detection in sample.

() = Laboratory InHouse Limit