

Report of Analysis

Client:	Union Paving & Construction Company		Date Collected:	06/23/25	
Project:	190 Park Ave Hanover Twp NJ - PO 2556-001		Date Received:	06/23/25	
Client Sample ID:	PARK AVE -5		SDG No.:	Q2393	
Lab Sample ID:	Q2393-10		Matrix:	SOIL	
Analytical Method:	8260D		% Solid:	88.4	
Sample Wt/Vol:	4.54	Units: g	Final Vol:	5000	uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10	
GC Column:	RXI-624	ID : 0.25	Level :	LOW	
Prep Method :					

File ID/Qc Batch:	Dilution:	Prep Date	Date Analyzed	Prep Batch ID
VY022799.D	1		06/24/25 15:52	VY062425

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
TARGETS						
75-71-8	Dichlorodifluoromethane	1.40	U	1.40	6.20	ug/Kg
74-87-3	Chloromethane	1.40	U	1.40	6.20	ug/Kg
75-01-4	Vinyl Chloride	0.98	U	0.98	6.20	ug/Kg
74-83-9	Bromomethane	1.30	U	1.30	6.20	ug/Kg
75-00-3	Chloroethane	1.60	U	1.60	6.20	ug/Kg
75-69-4	Trichlorofluoromethane	2.80	J	1.50	6.20	ug/Kg
76-13-1	1,1,2-Trichlorotrifluoroethane	1.30	U	1.30	6.20	ug/Kg
75-35-4	1,1-Dichloroethene	1.20	U	1.20	6.20	ug/Kg
67-64-1	Acetone	11.6	J	5.90	31.1	ug/Kg
75-15-0	Carbon Disulfide	1.30	U	1.30	6.20	ug/Kg
1634-04-4	Methyl tert-butyl Ether	0.91	U	0.91	6.20	ug/Kg
79-20-9	Methyl Acetate	1.90	U	1.90	6.20	ug/Kg
75-09-2	Methylene Chloride	4.40	U	4.40	12.5	ug/Kg
156-60-5	trans-1,2-Dichloroethene	1.10	U	1.10	6.20	ug/Kg
75-34-3	1,1-Dichloroethane	1.00	U	1.00	6.20	ug/Kg
110-82-7	Cyclohexane	0.98	U	0.98	6.20	ug/Kg
78-93-3	2-Butanone	8.10	U	8.10	31.1	ug/Kg
56-23-5	Carbon Tetrachloride	1.20	U	1.20	6.20	ug/Kg
156-59-2	cis-1,2-Dichloroethene	0.93	U	0.93	6.20	ug/Kg
74-97-5	Bromochloromethane	1.40	U	1.40	6.20	ug/Kg
67-66-3	Chloroform	1.00	U	1.00	6.20	ug/Kg
71-55-6	1,1,1-Trichloroethane	1.20	U	1.20	6.20	ug/Kg
108-87-2	Methylcyclohexane	1.10	U	1.10	6.20	ug/Kg
71-43-2	Benzene	0.98	U	0.98	6.20	ug/Kg
107-06-2	1,2-Dichloroethane	0.98	U	0.98	6.20	ug/Kg
79-01-6	Trichloroethene	1.00	U	1.00	6.20	ug/Kg
78-87-5	1,2-Dichloropropane	1.10	U	1.10	6.20	ug/Kg
75-27-4	Bromodichloromethane	0.97	U	0.97	6.20	ug/Kg
108-10-1	4-Methyl-2-Pentanone	4.50	U	4.50	31.1	ug/Kg
108-88-3	Toluene	0.97	U	0.97	6.20	ug/Kg

Report of Analysis

Client:	Union Paving & Construction Company		Date Collected:	06/23/25	
Project:	190 Park Ave Hanover Twp NJ - PO 2556-001		Date Received:	06/23/25	
Client Sample ID:	PARK AVE -5		SDG No.:	Q2393	
Lab Sample ID:	Q2393-10		Matrix:	SOIL	
Analytical Method:	8260D		% Solid:	88.4	
Sample Wt/Vol:	4.54	Units: g	Final Vol:	5000	uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10	
GC Column:	RXI-624	ID : 0.25	Level :	LOW	
Prep Method :					

File ID/Qc Batch:	Dilution:	Prep Date	Date Analyzed	Prep Batch ID
VY022799.D	1		06/24/25 15:52	VY062425

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
10061-02-6	t-1,3-Dichloropropene	0.81	U	0.81	6.20	ug/Kg
10061-01-5	cis-1,3-Dichloropropene	0.77	U	0.77	6.20	ug/Kg
79-00-5	1,1,2-Trichloroethane	1.10	U	1.10	6.20	ug/Kg
591-78-6	2-Hexanone	4.60	U	4.60	31.1	ug/Kg
124-48-1	Dibromochloromethane	1.10	U	1.10	6.20	ug/Kg
106-93-4	1,2-Dibromoethane	1.10	U	1.10	6.20	ug/Kg
127-18-4	Tetrachloroethene	1.30	U	1.30	6.20	ug/Kg
108-90-7	Chlorobenzene	1.10	U	1.10	6.20	ug/Kg
100-41-4	Ethyl Benzene	0.83	U	0.83	6.20	ug/Kg
179601-23-1	m/p-Xylenes	1.50	U	1.50	12.5	ug/Kg
95-47-6	o-Xylene	1.00	U	1.00	6.20	ug/Kg
100-42-5	Styrene	0.88	U	0.88	6.20	ug/Kg
75-25-2	Bromoform	1.10	U	1.10	6.20	ug/Kg
98-82-8	Isopropylbenzene	0.97	U	0.97	6.20	ug/Kg
79-34-5	1,1,2,2-Tetrachloroethane	1.50	U	1.50	6.20	ug/Kg
541-73-1	1,3-Dichlorobenzene	2.10	U	2.10	6.20	ug/Kg
106-46-7	1,4-Dichlorobenzene	1.90	U	1.90	6.20	ug/Kg
95-50-1	1,2-Dichlorobenzene	1.80	U	1.80	6.20	ug/Kg
96-12-8	1,2-Dibromo-3-Chloropropane	2.30	U	2.30	6.20	ug/Kg
120-82-1	1,2,4-Trichlorobenzene	3.70	U	3.70	6.20	ug/Kg
87-61-6	1,2,3-Trichlorobenzene	4.00	U	4.00	6.20	ug/Kg
SURROGATES						
17060-07-0	1,2-Dichloroethane-d4	46.8		63 - 155	94%	SPK: 50
1868-53-7	Dibromofluoromethane	49.1		70 - 134	98%	SPK: 50
2037-26-5	Toluene-d8	48.5		74 - 123	97%	SPK: 50
460-00-4	4-Bromofluorobenzene	51.6		17 - 146	103%	SPK: 50
INTERNAL STANDARDS						
363-72-4	Pentafluorobenzene	317000	7.707			
540-36-3	1,4-Difluorobenzene	576000	8.61			
3114-55-4	Chlorobenzene-d5	531000	11.414			
3855-82-1	1,4-Dichlorobenzene-d4	229000	13.34			

Report of Analysis

Client:	Union Paving & Construction Company		Date Collected:	06/23/25	
Project:	190 Park Ave Hanover Twp NJ - PO 2556-001		Date Received:	06/23/25	
Client Sample ID:	PARK AVE -5		SDG No.:	Q2393	
Lab Sample ID:	Q2393-10		Matrix:	SOIL	
Analytical Method:	8260D		% Solid:	88.4	
Sample Wt/Vol:	4.54	Units: g	Final Vol:	5000	uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10	
GC Column:	RXI-624	ID : 0.25	Level :	LOW	
Prep Method :					

File ID/Qc Batch:	Dilution:	Prep Date	Date Analyzed	Prep Batch ID
VY022799.D	1		06/24/25 15:52	VY062425

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units
------------	-----------	-------	-----------	-----	------------	-------

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

E = Value Exceeds Calibration Range

Q = indicates LCS control criteria did not meet requirements

M = MS/MSD acceptance criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

N = Presumptive Evidence of a Compound

* = Values outside of QC limits

D = Dilution

() = Laboratory InHouse Limit

A = Aldol-Condensation Reaction Products