

Report of Analysis

Client:	Coppola Services	Date Collected:	06/24/25
Project:	Millville Sewage Treatment Plant - Field Sampling	Date Received:	06/24/25
Client Sample ID:	COP-SOIL-PILE	SDG No.:	Q2409
Lab Sample ID:	Q2409-02	Matrix:	TCLP
Level (low/med):	low	% Solid:	0

Cas	Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units	Prep Date	Date Ana.	Ana Met.	Prep Met.
7440-38-2	Arsenic	25.6	U	1	25.6	100	ug/L	06/25/25 12:32	06/26/25 19:35	6010D	SW3050
7440-39-3	Barium	765		1	72.8	500	ug/L	06/25/25 12:32	06/26/25 19:35	6010D	SW3050
7440-43-9	Cadmium	65.9		1	2.50	30.0	ug/L	06/25/25 12:32	06/26/25 19:35	6010D	SW3050
7440-47-3	Chromium	11.8	J	1	10.6	50.0	ug/L	06/25/25 12:32	06/26/25 19:35	6010D	SW3050
7440-50-8	Copper	85.3	J	1	23.0	100	ug/L	06/25/25 12:32	06/26/25 19:35	6010D	SW3050
7439-92-1	Lead	155		1	11.5	60.0	ug/L	06/25/25 12:32	06/26/25 19:35	6010D	SW3050
7439-97-6	Mercury	0.76	U	1	0.76	2.00	ug/L	06/26/25 08:35	06/26/25 13:17	7470A	
7440-02-0	Nickel	15.3	U	1	15.3	200	ug/L	06/25/25 12:32	06/26/25 19:35	6010D	SW3050
7782-49-2	Selenium	48.2	U	1	48.2	100	ug/L	06/25/25 12:32	06/26/25 19:35	6010D	SW3050
7440-22-4	Silver	8.10	U	1	8.10	50.0	ug/L	06/25/25 12:32	06/26/25 19:35	6010D	SW3050
7440-66-6	Zinc	580		1	17.5	200	ug/L	06/25/25 12:32	06/26/25 19:35	6010D	SW3050

Color Before:	Colorless	Clarity Before:	Clear	Texture:
Color After:	Colorless	Clarity After:	Clear	Artifacts:
Comments:	TCLP Metals+Cu+Ni+Zn			

U = Not Detected
 LOQ = Limit of Quantitation
 MDL = Method Detection Limit
 LOD = Limit of Detection
 D = Dilution
 Q = indicates LCS control criteria did not meet requirements

J = Estimated Value
 B = Analyte Found in Associated Method Blank
 * = indicates the duplicate analysis is not within control limits.
 E = Indicates the reported value is estimated because of the presence of interference.
 OR = Over Range
 N =Spiked sample recovery not within control limits