

Report of Analysis

Client:	Walsh Construction Company II, LLC	Date Collected:	07/01/25 11:00
Project:	Construction of Shafts 17B-18B - PN 220084	Date Received:	07/01/25
Client Sample ID:	G4(0-6)	SDG No.:	Q2489
Lab Sample ID:	Q2489-01	Matrix:	SOIL
		% Solid:	100

Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units	Prep Date	Date Ana.	Ana Met.
Corrosivity	7.73	H	1	0	0	pH		07/03/25 15:30	9045D
Ignitability	NO		1	0	0	oC		07/03/25 08:55	1030
Reactive Cyanide	0.0083	U	1	0.0083	0.050	mg/Kg	07/07/25 14:00	07/07/25 16:05	9012B
Reactive Sulfide	4.72	J	1	0.20	10.0	mg/Kg	07/07/25 15:50	07/08/25 09:33	9034

Comments: pH result reported at temperature 20.7 °C

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

D = Dilution

Q = indicates LCS control criteria did not meet requirements

H = Sample Analysis Out Of Hold Time

J = Estimated Value

B = Analyte Found in Associated Method Blank

* = indicates the duplicate analysis is not within control limits.

E = Indicates the reported value is estimated because of the presence of interference.

OR = Over Range

N =Spiked sample recovery not within control limits