

Report of Analysis

Client:	T&A Construction Inc		Date Collected:	07/14/25	
Project:	Kingsland Point Park Water Main		Date Received:	07/14/25	
Client Sample ID:	END-OF-TRENCH		SDG No.:	Q2600	
Lab Sample ID:	Q2600-12		Matrix:	TCLP	
Analytical Method:	8260D		% Solid:	0	
Sample Wt/Vol:	5	Units: mL	Final Vol:	5000	uL
Soil Aliquot Vol:		uL	Test:	TCLP VOA	
GC Column:	DB-624UI	ID : 0.18	Level :	LOW	
Prep Method :	SW5035				

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VX047028.D	1	07/16/25 14:24	VX071625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units
TARGETS						
75-01-4	Vinyl Chloride	0.26	U	0.26	5.00	ug/L
75-35-4	1,1-Dichloroethene	0.23	U	0.23	5.00	ug/L
78-93-3	2-Butanone	7.00	JQ	0.98	25.0	ug/L
56-23-5	Carbon Tetrachloride	0.25	U	0.25	5.00	ug/L
67-66-3	Chloroform	0.25	U	0.25	5.00	ug/L
71-43-2	Benzene	1.20	J	0.15	5.00	ug/L
107-06-2	1,2-Dichloroethane	0.22	U	0.22	5.00	ug/L
79-01-6	Trichloroethene	0.090	U	0.090	5.00	ug/L
127-18-4	Tetrachloroethene	0.23	U	0.23	5.00	ug/L
108-90-7	Chlorobenzene	0.12	U	0.12	5.00	ug/L
SURROGATES						
17060-07-0	1,2-Dichloroethane-d4	51.2		74 - 125	102%	SPK: 50
1868-53-7	Dibromofluoromethane	47.6		75 - 124	95%	SPK: 50
2037-26-5	Toluene-d8	49.3		86 - 113	99%	SPK: 50
460-00-4	4-Bromofluorobenzene	53.0		77 - 121	106%	SPK: 50
INTERNAL STANDARDS						
363-72-4	Pentafluorobenzene	368000	5.568			
540-36-3	1,4-Difluorobenzene	639000	6.769			
3114-55-4	Chlorobenzene-d5	581000	10.055			
3855-82-1	1,4-Dichlorobenzene-d4	283000	12.018			

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

E = Value Exceeds Calibration Range

Q = indicates LCS control criteria did not meet requirements

M = MS/MSD acceptance criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

N = Presumptive Evidence of a Compound

* = Values outside of QC limits

D = Dilution

() = Laboratory InHouse Limit

A = Aldol-Condensation Reaction Products