

Hit Summary Sheet
SW-846

SDG No.: Q2600
Client: T&A Construction Inc

Sample ID	Client ID	Matrix	Parameter	Concentration	C	MDL	RDL	Units
Client ID: Q2600-04	TRENCH TRENCH	TCLP	2-Butanone	5.70	JQ	0.98	25.0	ug/L
			Total Voc :	5.70				
			Total Concentration:	5.70				
Client ID: Q2600-08	STOCK-PILE STOCK-PILE	TCLP	2-Butanone	6.60	JQ	0.98	25.0	ug/L
			Total Voc :	6.60				
			Total Concentration:	6.60				
Client ID: Q2600-12	END-OF-TRENCH END-OF-TRENCH	TCLP	2-Butanone	7.00	JQ	0.98	25.0	ug/L
Q2600-12	END-OF-TRENCH	TCLP	Benzene	1.20	J	0.15	5.00	ug/L
			Total Voc :	8.20				
			Total Concentration:	8.20				



SAMPLE DATA

A

B

C

D

Report of Analysis

Client:	T&A Construction Inc	Date Collected:	07/14/25
Project:	Kingsland Point Park Water Main	Date Received:	07/14/25
Client Sample ID:	TRENCH	SDG No.:	Q2600
Lab Sample ID:	Q2600-04	Matrix:	TCLP
Analytical Method:	8260D	% Solid:	0
Sample Wt/Vol:	5 Units: mL	Final Vol:	5000 uL
Soil Aliquot Vol:	uL	Test:	TCLP VOA
GC Column:	DB-624UI ID : 0.18	Level :	LOW
Prep Method :	SW5035		

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VX047026.D	1	07/16/25 13:42	VX071625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units
TARGETS						
75-01-4	Vinyl Chloride	0.26	U	0.26	5.00	ug/L
75-35-4	1,1-Dichloroethene	0.23	U	0.23	5.00	ug/L
78-93-3	2-Butanone	5.70	JQ	0.98	25.0	ug/L
56-23-5	Carbon Tetrachloride	0.25	U	0.25	5.00	ug/L
67-66-3	Chloroform	0.25	U	0.25	5.00	ug/L
71-43-2	Benzene	0.15	U	0.15	5.00	ug/L
107-06-2	1,2-Dichloroethane	0.22	U	0.22	5.00	ug/L
79-01-6	Trichloroethene	0.090	U	0.090	5.00	ug/L
127-18-4	Tetrachloroethene	0.23	U	0.23	5.00	ug/L
108-90-7	Chlorobenzene	0.12	U	0.12	5.00	ug/L
SURROGATES						
17060-07-0	1,2-Dichloroethane-d4	53.4		74 - 125	107%	SPK: 50
1868-53-7	Dibromofluoromethane	48.0		75 - 124	96%	SPK: 50
2037-26-5	Toluene-d8	50.0		86 - 113	100%	SPK: 50
460-00-4	4-Bromofluorobenzene	55.1		77 - 121	110%	SPK: 50
INTERNAL STANDARDS						
363-72-4	Pentafluorobenzene	456000	5.562			
540-36-3	1,4-Difluorobenzene	802000	6.769			
3114-55-4	Chlorobenzene-d5	756000	10.055			
3855-82-1	1,4-Dichlorobenzene-d4	387000	12.018			

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

E = Value Exceeds Calibration Range

Q = indicates LCS control criteria did not meet requirements

M = MS/MSD acceptance criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

N = Presumptive Evidence of a Compound

* = Values outside of QC limits

D = Dilution

() = Laboratory InHouse Limit

A = Aldol-Condensation Reaction Products

Report of Analysis

Client:	T&A Construction Inc	Date Collected:	07/14/25
Project:	Kingsland Point Park Water Main	Date Received:	07/14/25
Client Sample ID:	STOCK-PILE	SDG No.:	Q2600
Lab Sample ID:	Q2600-08	Matrix:	TCLP
Analytical Method:	8260D	% Solid:	0
Sample Wt/Vol:	5 Units: mL	Final Vol:	5000 uL
Soil Aliquot Vol:	uL	Test:	TCLP VOA
GC Column:	DB-624UI ID : 0.18	Level :	LOW
Prep Method :	SW5035		

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VX047027.D	1	07/16/25 14:03	VX071625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units
TARGETS						
75-01-4	Vinyl Chloride	0.26	U	0.26	5.00	ug/L
75-35-4	1,1-Dichloroethene	0.23	U	0.23	5.00	ug/L
78-93-3	2-Butanone	6.60	JQ	0.98	25.0	ug/L
56-23-5	Carbon Tetrachloride	0.25	U	0.25	5.00	ug/L
67-66-3	Chloroform	0.25	U	0.25	5.00	ug/L
71-43-2	Benzene	0.15	U	0.15	5.00	ug/L
107-06-2	1,2-Dichloroethane	0.22	U	0.22	5.00	ug/L
79-01-6	Trichloroethene	0.090	U	0.090	5.00	ug/L
127-18-4	Tetrachloroethene	0.23	U	0.23	5.00	ug/L
108-90-7	Chlorobenzene	0.12	U	0.12	5.00	ug/L
SURROGATES						
17060-07-0	1,2-Dichloroethane-d4	55.0		74 - 125	110%	SPK: 50
1868-53-7	Dibromofluoromethane	48.9		75 - 124	98%	SPK: 50
2037-26-5	Toluene-d8	50.7		86 - 113	101%	SPK: 50
460-00-4	4-Bromofluorobenzene	55.5		77 - 121	111%	SPK: 50
INTERNAL STANDARDS						
363-72-4	Pentafluorobenzene	467000	5.568			
540-36-3	1,4-Difluorobenzene	838000	6.769			
3114-55-4	Chlorobenzene-d5	804000	10.055			
3855-82-1	1,4-Dichlorobenzene-d4	413000	12.018			

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

E = Value Exceeds Calibration Range

Q = indicates LCS control criteria did not meet requirements

M = MS/MSD acceptance criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

N = Presumptive Evidence of a Compound

* = Values outside of QC limits

D = Dilution

() = Laboratory InHouse Limit

A = Aldol-Condensation Reaction Products

Report of Analysis

Client:	T&A Construction Inc	Date Collected:	07/14/25
Project:	Kingsland Point Park Water Main	Date Received:	07/14/25
Client Sample ID:	END-OF-TRENCH	SDG No.:	Q2600
Lab Sample ID:	Q2600-12	Matrix:	TCLP
Analytical Method:	8260D	% Solid:	0
Sample Wt/Vol:	5 Units: mL	Final Vol:	5000 uL
Soil Aliquot Vol:	uL	Test:	TCLP VOA
GC Column:	DB-624UI ID : 0.18	Level :	LOW
Prep Method :	SW5035		

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VX047028.D	1	07/16/25 14:24	VX071625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units
TARGETS						
75-01-4	Vinyl Chloride	0.26	U	0.26	5.00	ug/L
75-35-4	1,1-Dichloroethene	0.23	U	0.23	5.00	ug/L
78-93-3	2-Butanone	7.00	JQ	0.98	25.0	ug/L
56-23-5	Carbon Tetrachloride	0.25	U	0.25	5.00	ug/L
67-66-3	Chloroform	0.25	U	0.25	5.00	ug/L
71-43-2	Benzene	1.20	J	0.15	5.00	ug/L
107-06-2	1,2-Dichloroethane	0.22	U	0.22	5.00	ug/L
79-01-6	Trichloroethene	0.090	U	0.090	5.00	ug/L
127-18-4	Tetrachloroethene	0.23	U	0.23	5.00	ug/L
108-90-7	Chlorobenzene	0.12	U	0.12	5.00	ug/L
SURROGATES						
17060-07-0	1,2-Dichloroethane-d4	51.2		74 - 125	102%	SPK: 50
1868-53-7	Dibromofluoromethane	47.6		75 - 124	95%	SPK: 50
2037-26-5	Toluene-d8	49.3		86 - 113	99%	SPK: 50
460-00-4	4-Bromofluorobenzene	53.0		77 - 121	106%	SPK: 50
INTERNAL STANDARDS						
363-72-4	Pentafluorobenzene	368000	5.568			
540-36-3	1,4-Difluorobenzene	639000	6.769			
3114-55-4	Chlorobenzene-d5	581000	10.055			
3855-82-1	1,4-Dichlorobenzene-d4	283000	12.018			

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

E = Value Exceeds Calibration Range

Q = indicates LCS control criteria did not meet requirements

M = MS/MSD acceptance criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

N = Presumptive Evidence of a Compound

* = Values outside of QC limits

D = Dilution

() = Laboratory InHouse Limit

A = Aldol-Condensation Reaction Products

LAB CHRONICLE

OrderID:	Q2600	OrderDate:	7/14/2025 2:21:01 PM
Client:	T&A Construction Inc	Project:	Kingsland Point Park Water Main
Contact:	Garrett Johnson	Location:	D41,VOA Ref. #2 Soil

LabID	ClientID	Matrix	Test	Method	Sample Date	Prep Date	Anal Date	Received
Q2600-03	TRENCH	SOIL	VOC-TCLVOA-10	8260D	07/14/25		07/15/25	07/14/25
Q2600-04	TRENCH	TCLP	TCLP VOA	8260D	07/14/25		07/16/25	07/14/25
Q2600-07	STOCK-PILE	SOIL	VOC-TCLVOA-10	8260D	07/14/25		07/15/25	07/14/25
Q2600-08	STOCK-PILE	TCLP	TCLP VOA	8260D	07/14/25		07/16/25	07/14/25
Q2600-11	END-OF-TRENCH	SOIL	VOC-TCLVOA-10	8260D	07/14/25		07/15/25	07/14/25
Q2600-11DL	END-OF-TRENCHDL	SOIL	VOC-TCLVOA-10	8260D	07/14/25		07/16/25	07/14/25
Q2600-12	END-OF-TRENCH	TCLP	TCLP VOA	8260D	07/14/25		07/16/25	07/14/25