

Report of Analysis

Client:	Sciacca General Contractors, LLC		Date Collected:	
Project:	166 Belmont Ave Belleville		Date Received:	
Client Sample ID:	VW0716SBL01		SDG No.:	Q2618
Lab Sample ID:	VW0716SBL01		Matrix:	SOIL
Analytical Method:	8260D		% Solid:	100
Sample Wt/Vol:	5	Units: g	Final Vol:	5000 uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10
GC Column:	RXI-624	ID : 0.25	Level :	LOW
Prep Method :				

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VW031865.D	1	07/16/25 09:52	VW071625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
TARGETS						
75-71-8	Dichlorodifluoromethane	1.10	U	1.10	5.00	ug/Kg
74-87-3	Chloromethane	1.10	U	1.10	5.00	ug/Kg
75-01-4	Vinyl Chloride	0.79	U	0.79	5.00	ug/Kg
74-83-9	Bromomethane	1.10	U	1.10	5.00	ug/Kg
75-00-3	Chloroethane	1.30	U	1.30	5.00	ug/Kg
75-69-4	Trichlorofluoromethane	1.20	U	1.20	5.00	ug/Kg
76-13-1	1,1,2-Trichlorotrifluoroethane	1.10	U	1.10	5.00	ug/Kg
75-35-4	1,1-Dichloroethene	1.00	U	1.00	5.00	ug/Kg
67-64-1	Acetone	4.70	U	4.70	25.0	ug/Kg
75-15-0	Carbon Disulfide	1.10	U	1.10	5.00	ug/Kg
1634-04-4	Methyl tert-butyl Ether	0.73	U	0.73	5.00	ug/Kg
79-20-9	Methyl Acetate	1.50	U	1.50	5.00	ug/Kg
75-09-2	Methylene Chloride	3.50	U	3.50	10.0	ug/Kg
156-60-5	trans-1,2-Dichloroethene	0.86	U	0.86	5.00	ug/Kg
75-34-3	1,1-Dichloroethane	0.80	U	0.80	5.00	ug/Kg
110-82-7	Cyclohexane	0.79	U	0.79	5.00	ug/Kg
78-93-3	2-Butanone	6.50	U	6.50	25.0	ug/Kg
56-23-5	Carbon Tetrachloride	0.97	U	0.97	5.00	ug/Kg
156-59-2	cis-1,2-Dichloroethene	0.75	U	0.75	5.00	ug/Kg
74-97-5	Bromochloromethane	1.20	U	1.20	5.00	ug/Kg
67-66-3	Chloroform	0.84	U	0.84	5.00	ug/Kg
71-55-6	1,1,1-Trichloroethane	0.93	U	0.93	5.00	ug/Kg
108-87-2	Methylcyclohexane	0.91	U	0.91	5.00	ug/Kg
71-43-2	Benzene	0.79	U	0.79	5.00	ug/Kg
107-06-2	1,2-Dichloroethane	0.79	U	0.79	5.00	ug/Kg
79-01-6	Trichloroethene	0.81	U	0.81	5.00	ug/Kg
78-87-5	1,2-Dichloropropane	0.91	U	0.91	5.00	ug/Kg
75-27-4	Bromodichloromethane	0.78	U	0.78	5.00	ug/Kg
108-10-1	4-Methyl-2-Pentanone	3.60	U	3.60	25.0	ug/Kg
108-88-3	Toluene	0.78	U	0.78	5.00	ug/Kg

Report of Analysis

Client:	Sciacca General Contractors, LLC		Date Collected:	
Project:	166 Belmont Ave Belleville		Date Received:	
Client Sample ID:	VW0716SBL01		SDG No.:	Q2618
Lab Sample ID:	VW0716SBL01		Matrix:	SOIL
Analytical Method:	8260D		% Solid:	100
Sample Wt/Vol:	5	Units: g	Final Vol:	5000 uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10
GC Column:	RXI-624	ID : 0.25	Level :	LOW
Prep Method :				

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VW031865.D	1	07/16/25 09:52	VW071625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
10061-02-6	t-1,3-Dichloropropene	0.65	U	0.65	5.00	ug/Kg
10061-01-5	cis-1,3-Dichloropropene	0.62	U	0.62	5.00	ug/Kg
79-00-5	1,1,2-Trichloroethane	0.92	U	0.92	5.00	ug/Kg
591-78-6	2-Hexanone	3.70	U	3.70	25.0	ug/Kg
124-48-1	Dibromochloromethane	0.87	U	0.87	5.00	ug/Kg
106-93-4	1,2-Dibromoethane	0.88	U	0.88	5.00	ug/Kg
127-18-4	Tetrachloroethene	1.10	U	1.10	5.00	ug/Kg
108-90-7	Chlorobenzene	0.91	U	0.91	5.00	ug/Kg
100-41-4	Ethyl Benzene	0.67	U	0.67	5.00	ug/Kg
179601-23-1	m/p-Xylenes	1.20	U	1.20	10.0	ug/Kg
95-47-6	o-Xylene	0.82	U	0.82	5.00	ug/Kg
100-42-5	Styrene	0.71	U	0.71	5.00	ug/Kg
75-25-2	Bromoform	0.86	U	0.86	5.00	ug/Kg
98-82-8	Isopropylbenzene	0.78	U	0.78	5.00	ug/Kg
79-34-5	1,1,2,2-Tetrachloroethane	1.20	U	1.20	5.00	ug/Kg
541-73-1	1,3-Dichlorobenzene	1.70	U	1.70	5.00	ug/Kg
106-46-7	1,4-Dichlorobenzene	1.60	U	1.60	5.00	ug/Kg
95-50-1	1,2-Dichlorobenzene	1.50	U	1.50	5.00	ug/Kg
96-12-8	1,2-Dibromo-3-Chloropropane	1.80	U	1.80	5.00	ug/Kg
120-82-1	1,2,4-Trichlorobenzene	3.00	U	3.00	5.00	ug/Kg
87-61-6	1,2,3-Trichlorobenzene	3.20	U	3.20	5.00	ug/Kg
SURROGATES						
17060-07-0	1,2-Dichloroethane-d4	46.8		63 - 155	94%	SPK: 50
1868-53-7	Dibromofluoromethane	45.2		70 - 134	90%	SPK: 50
2037-26-5	Toluene-d8	44.1		74 - 123	88%	SPK: 50
460-00-4	4-Bromofluorobenzene	46.1		17 - 146	92%	SPK: 50
INTERNAL STANDARDS						
363-72-4	Pentafluorobenzene	186000	7.965			
540-36-3	1,4-Difluorobenzene	375000	8.849			
3114-55-4	Chlorobenzene-d5	352000	11.629			
3855-82-1	1,4-Dichlorobenzene-d4	164000	13.556			

Report of Analysis

Client:	Sciacca General Contractors, LLC		Date Collected:	
Project:	166 Belmont Ave Belleville		Date Received:	
Client Sample ID:	VW0716SBL01		SDG No.:	Q2618
Lab Sample ID:	VW0716SBL01		Matrix:	SOIL
Analytical Method:	8260D		% Solid:	100
Sample Wt/Vol:	5	Units: g	Final Vol:	5000 uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10
GC Column:	RXI-624	ID : 0.25	Level :	LOW
Prep Method :				

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VW031865.D	1	07/16/25 09:52	VW071625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units
------------	-----------	-------	-----------	-----	------------	-------

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

E = Value Exceeds Calibration Range

Q = indicates LCS control criteria did not meet requirements

M = MS/MSD acceptance criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

N = Presumptive Evidence of a Compound

* = Values outside of QC limits

D = Dilution

() = Laboratory InHouse Limit

A = Aldol-Condensation Reaction Products