

Report of Analysis

Client:	Sciacca General Contractors, LLC		Date Collected:	
Project:	92 Clifford Street, Newark		Date Received:	
Client Sample ID:	VW0804SBS01		SDG No.:	Q2758
Lab Sample ID:	VW0804SBS01		Matrix:	SOIL
Analytical Method:	8260D		% Solid:	100
Sample Wt/Vol:	5	Units: g	Final Vol:	5000 uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10
GC Column:	RXI-624	ID : 0.25	Level :	LOW
Prep Method :				

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VW031989.D	1	08/04/25 10:20	VW080425

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
TARGETS						
75-71-8	Dichlorodifluoromethane	17.3		1.10	5.00	ug/Kg
74-87-3	Chloromethane	19.6		1.10	5.00	ug/Kg
75-01-4	Vinyl Chloride	17.7		0.79	5.00	ug/Kg
74-83-9	Bromomethane	18.8		1.10	5.00	ug/Kg
75-00-3	Chloroethane	19.9		1.30	5.00	ug/Kg
75-69-4	Trichlorofluoromethane	15.1		1.20	5.00	ug/Kg
76-13-1	1,1,2-Trichlorotrifluoroethane	19.8		1.10	5.00	ug/Kg
75-35-4	1,1-Dichloroethene	19.0		1.00	5.00	ug/Kg
67-64-1	Acetone	120		4.70	25.0	ug/Kg
75-15-0	Carbon Disulfide	18.6		1.10	5.00	ug/Kg
1634-04-4	Methyl tert-butyl Ether	19.9		0.73	5.00	ug/Kg
79-20-9	Methyl Acetate	19.8		1.50	5.00	ug/Kg
75-09-2	Methylene Chloride	16.6		3.50	10.0	ug/Kg
156-60-5	trans-1,2-Dichloroethene	19.1		0.86	5.00	ug/Kg
75-34-3	1,1-Dichloroethane	19.6		0.80	5.00	ug/Kg
110-82-7	Cyclohexane	18.0		0.79	5.00	ug/Kg
78-93-3	2-Butanone	100		6.50	25.0	ug/Kg
56-23-5	Carbon Tetrachloride	20.1		0.97	5.00	ug/Kg
156-59-2	cis-1,2-Dichloroethene	19.5		0.75	5.00	ug/Kg
74-97-5	Bromochloromethane	19.9		1.20	5.00	ug/Kg
67-66-3	Chloroform	20.4		0.84	5.00	ug/Kg
71-55-6	1,1,1-Trichloroethane	20.2		0.93	5.00	ug/Kg
108-87-2	Methylcyclohexane	18.5		0.91	5.00	ug/Kg
71-43-2	Benzene	20.4		0.79	5.00	ug/Kg
107-06-2	1,2-Dichloroethane	20.0		0.79	5.00	ug/Kg
79-01-6	Trichloroethene	20.4		0.81	5.00	ug/Kg
78-87-5	1,2-Dichloropropane	20.2		0.91	5.00	ug/Kg
75-27-4	Bromodichloromethane	20.6		0.78	5.00	ug/Kg
108-10-1	4-Methyl-2-Pentanone	95.7		3.60	25.0	ug/Kg
108-88-3	Toluene	20.2		0.78	5.00	ug/Kg

Report of Analysis

Client:	Sciacca General Contractors, LLC		Date Collected:	
Project:	92 Clifford Street, Newark		Date Received:	
Client Sample ID:	VW0804SBS01		SDG No.:	Q2758
Lab Sample ID:	VW0804SBS01		Matrix:	SOIL
Analytical Method:	8260D		% Solid:	100
Sample Wt/Vol:	5	Units: g	Final Vol:	5000 uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10
GC Column:	RXI-624	ID : 0.25	Level :	LOW
Prep Method :				

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VW031989.D	1	08/04/25 10:20	VW080425

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
10061-02-6	t-1,3-Dichloropropene	19.4		0.65	5.00	ug/Kg
10061-01-5	cis-1,3-Dichloropropene	20.2		0.62	5.00	ug/Kg
79-00-5	1,1,2-Trichloroethane	20.3		0.92	5.00	ug/Kg
591-78-6	2-Hexanone	99.1		3.70	25.0	ug/Kg
124-48-1	Dibromochloromethane	20.6		0.87	5.00	ug/Kg
106-93-4	1,2-Dibromoethane	19.7		0.88	5.00	ug/Kg
127-18-4	Tetrachloroethene	20.5		1.10	5.00	ug/Kg
108-90-7	Chlorobenzene	19.6		0.91	5.00	ug/Kg
100-41-4	Ethyl Benzene	19.3		0.67	5.00	ug/Kg
179601-23-1	m/p-Xylenes	39.5		1.20	10.0	ug/Kg
95-47-6	o-Xylene	19.7		0.82	5.00	ug/Kg
100-42-5	Styrene	20.2		0.71	5.00	ug/Kg
75-25-2	Bromoform	19.3		0.86	5.00	ug/Kg
98-82-8	Isopropylbenzene	18.4		0.78	5.00	ug/Kg
79-34-5	1,1,2,2-Tetrachloroethane	18.5		1.20	5.00	ug/Kg
541-73-1	1,3-Dichlorobenzene	19.3		1.70	5.00	ug/Kg
106-46-7	1,4-Dichlorobenzene	19.4		1.60	5.00	ug/Kg
95-50-1	1,2-Dichlorobenzene	19.8		1.50	5.00	ug/Kg
96-12-8	1,2-Dibromo-3-Chloropropane	17.3		1.80	5.00	ug/Kg
120-82-1	1,2,4-Trichlorobenzene	19.8		3.00	5.00	ug/Kg
87-61-6	1,2,3-Trichlorobenzene	18.9		3.20	5.00	ug/Kg
SURROGATES						
17060-07-0	1,2-Dichloroethane-d4	52.8		63 - 155	106%	SPK: 50
1868-53-7	Dibromofluoromethane	55.9		70 - 134	112%	SPK: 50
2037-26-5	Toluene-d8	55.6		74 - 123	111%	SPK: 50
460-00-4	4-Bromofluorobenzene	55.9		17 - 146	112%	SPK: 50
INTERNAL STANDARDS						
363-72-4	Pentafluorobenzene	212000	7.959			
540-36-3	1,4-Difluorobenzene	385000	8.849			
3114-55-4	Chlorobenzene-d5	350000	11.629			
3855-82-1	1,4-Dichlorobenzene-d4	171000	13.556			

Report of Analysis

Client:	Sciacca General Contractors, LLC		Date Collected:	
Project:	92 Clifford Street, Newark		Date Received:	
Client Sample ID:	VW0804SBS01		SDG No.:	Q2758
Lab Sample ID:	VW0804SBS01		Matrix:	SOIL
Analytical Method:	8260D		% Solid:	100
Sample Wt/Vol:	5	Units: g	Final Vol:	5000 uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10
GC Column:	RXI-624	ID : 0.25	Level :	LOW
Prep Method :				

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VW031989.D	1	08/04/25 10:20	VW080425

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units
------------	-----------	-------	-----------	-----	------------	-------

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

E = Value Exceeds Calibration Range

Q = indicates LCS control criteria did not meet requirements

M = MS/MSD acceptance criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

N = Presumptive Evidence of a Compound

* = Values outside of QC limits

D = Dilution

() = Laboratory InHouse Limit

A = Aldol-Condensation Reaction Products