



SAMPLE DATA

Report of Analysis

Client:	Earth Engineering Inc.	Date Collected:	08/11/25 08:50
Project:	Reserve Turgyan Farms	Date Received:	08/11/25
Client Sample ID:	B-2-5-1	SDG No.:	Q2818
Lab Sample ID:	Q2818-01	Matrix:	SOIL
		% Solid:	87.5

Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units(Dry Weight)	Prep Date	Date Ana.	Ana Met.
Cyanide	0.40		1	0.048	0.28	mg/Kg	08/11/25 12:45	08/11/25 15:00	9012B
Hexavalent Chromium	0.079	U	1	0.079	0.45	mg/Kg	08/19/25 09:00	08/19/25 12:44	7196A

Comments: _____

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

D = Dilution

Q = indicates LCS control criteria did not meet requirements

H = Sample Analysis Out Of Hold Time

J = Estimated Value

B = Analyte Found in Associated Method Blank

* = indicates the duplicate analysis is not within control limits.

E = Indicates the reported value is estimated because of the presence of interference.

OR = Over Range

N =Spiked sample recovery not within control limits

Report of Analysis

Client:	Earth Engineering Inc.	Date Collected:	08/11/25 09:35
Project:	Reserve Turgyan Farms	Date Received:	08/11/25
Client Sample ID:	B-3-5-2	SDG No.:	Q2818
Lab Sample ID:	Q2818-02	Matrix:	SOIL
		% Solid:	89.1

Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units(Dry Weight)	Prep Date	Date Ana.	Ana Met.
Cyanide	0.33		1	0.045	0.27	mg/Kg	08/11/25 12:45	08/11/25 15:05	9012B
Hexavalent Chromium	0.078	U	1	0.078	0.45	mg/Kg	08/19/25 09:00	08/19/25 12:45	7196A

Comments: _____

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

D = Dilution

Q = indicates LCS control criteria did not meet requirements

H = Sample Analysis Out Of Hold Time

J = Estimated Value

B = Analyte Found in Associated Method Blank

* = indicates the duplicate analysis is not within control limits.

E = Indicates the reported value is estimated because of the presence of interference.

OR = Over Range

N =Spiked sample recovery not within control limits



QC RESULT SUMMARY

Initial and Continuing Calibration Verification

Client: Earth Engineering Inc.

SDG No.: Q2818

Project: Reserve Turgyan Farms

RunNo.: LB136777

Analyte		Units	Result	True Value	% Recovery	Acceptance Window (%R)	Analysis Date
Sample ID: Cyanide	ICV1	mg/L	0.096	0.099	97	90-110	08/11/2025
Sample ID: Cyanide	CCV1	mg/L	0.25	0.25	100	90-110	08/11/2025
Sample ID: Cyanide	CCV2	mg/L	0.25	0.25	100	90-110	08/11/2025

Initial and Continuing Calibration Verification

Client: Earth Engineering Inc.

SDG No.: Q2818

Project: Reserve Turgyan Farms

RunNo.: LB136872

Analyte	Units	Result	True Value	% Recovery	Acceptance Window (%R)	Analysis Date
Sample ID: ICV Hexavalent Chromium	mg/L	0.499	0.5	100	90-110	08/19/2025
Sample ID: CCV1 Hexavalent Chromium	mg/L	0.496	0.5	99	90-110	08/19/2025
Sample ID: CCV2 Hexavalent Chromium	mg/L	0.487	0.5	97	90-110	08/19/2025
Sample ID: CCV3 Hexavalent Chromium	mg/L	0.493	0.5	99	90-110	08/19/2025

Initial and Continuing Calibration Blank Summary

Client: Earth Engineering Inc.

SDG No.: Q2818

Project: Reserve Turgyan Farms

RunNo.: LB136777

Analyte	Units	Result	Acceptance Limits	Conc Qual	MDL	RDL	Analysis Date
Sample ID: ICB1 Cyanide	mg/L	0.0014	0.0025	J	0.00096	0.005	08/11/2025
Sample ID: CCB1 Cyanide	mg/L	0.0016	0.0025	J	0.00096	0.005	08/11/2025
Sample ID: CCB2 Cyanide	mg/L	0.0014	0.0025	J	0.00096	0.005	08/11/2025

Initial and Continuing Calibration Blank Summary

Client: Earth Engineering Inc.
Project: Reserve Turgyan Farms

SDG No.: Q2818
RunNo.: LB136872

Analyte	Units	Result	Acceptance Limits	Conc Qual	MDL	RDL	Analysis Date
Sample ID: ICB Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0029	0.01	08/19/2025
Sample ID: CCB1 Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0029	0.01	08/19/2025
Sample ID: CCB2 Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0029	0.01	08/19/2025
Sample ID: CCB3 Hexavalent Chromium	mg/L	< 0.0050	0.0050	U	0.0029	0.01	08/19/2025

Preparation Blank Summary

Client: Earth Engineering Inc.

SDG No.: Q2818

Project: Reserve Turgyan Farms

Analyte	Units	Result	Acceptance Limits	Conc Qual	MDL	RDL	Analysis Date
Sample ID: PB169197BL							
Cyanide	mg/Kg	0.057	0.1250	J	0.042	0.25	08/11/2025
Sample ID: PB169305BL							
Hexavalent Chromium	mg/Kg	< 0.2000	0.2000	U	0.07	0.4	08/19/2025

Matrix Spike Summary

Client:	Earth Engineering Inc.	SDG No.:	Q2818
Project:	Reserve Turgyan Farms	Sample ID:	Q2818-01
Client ID:	B-2-5-1MS	Percent Solids for Spike Sample:	87.5

Analyte	Units	Acceptance Limit %R	Spiked Result	Conc. Qualifier	Sample Result	Conc. Qualifier	Spike Added	Dilution Factor	% Rec	Qual	Analysis Date
Cyanide	mg/Kg	75-125	2.40		0.40		2.2	1	91		08/11/2025

Matrix Spike Summary

Client:	Earth Engineering Inc.	SDG No.:	Q2818
Project:	Reserve Turgyan Farms	Sample ID:	Q2818-01
Client ID:	B-2-5-1MSD	Percent Solids for Spike Sample:	87.5

Analyte	Units	Acceptance Limit %R	Spiked Result	Conc. Qualifier	Sample Result	Conc. Qualifier	Spike Added	Dilution Factor	% Rec	Qual	Analysis Date
Cyanide	mg/Kg	75-125	2.50		0.40		2.3	1	91		08/11/2025

Matrix Spike Summary

Client:	Earth Engineering Inc.	SDG No.:	Q2818
Project:	Reserve Turgyan Farms	Sample ID:	Q2888-01
Client ID:	VNJ-210MS	Percent Solids for Spike Sample:	94.9

Analyte	Units	Acceptance Limit %R	Spiked Result	Conc. Qualifier	Sample Result	Conc. Qualifier	Spike Added	Dilution Factor	% Rec	Qual	Analysis Date
Hexavalent Chromium	mg/Kg	75-125	1280		0.073	U	1350	40	95		08/19/2025

Matrix Spike Summary

Client:	Earth Engineering Inc.	SDG No.:	Q2818
Project:	Reserve Turgyan Farms	Sample ID:	Q2888-01
Client ID:	VNJ-210MS	Percent Solids for Spike Sample:	94.9

Analyte	Units	Acceptance Limit %R	Spiked Result	Conc. Qualifier	Sample Result	Conc. Qualifier	Spike Added	Dilution Factor	% Rec	Qual	Analysis Date
Hexavalent Chromium	mg/Kg	85-115	38.3		0.073	U	42.1	2	91		08/19/2025

Matrix Spike Summary

Client:	Earth Engineering Inc.	SDG No.:	Q2818
Project:	Reserve Turgyan Farms	Sample ID:	Q2888-01
Client ID:	VNJ-210MS	Percent Solids for Spike Sample:	94.9

Analyte	Units	Acceptance Limit %R	Spiked Result	Conc. Qualifier	Sample Result	Conc. Qualifier	Spike Added	Dilution Factor	% Rec	Qual	Analysis Date
Hexavalent Chromium	mg/Kg	75-125	33.4		0.073	U	42.1	2	79		08/19/2025

Duplicate Sample Summary

Client: Earth Engineering Inc. Project: Reserve Turgyan Farms Client ID: B-2-5-1DUP	SDG No.: Q2818 Sample ID: Q2818-01 Percent Solids for Spike Sample: 87.5
--	---

Analyte	Units	Acceptance Limit	Sample Result	Conc. Qualifier	Duplicate Result	Conc. Qualifier	Dilution Factor	RPD/ AD	Qual	Analysis Date
Cyanide	mg/Kg	+/-20	0.40		0.39		1	3		08/11/2025

Duplicate Sample Summary

Client: Earth Engineering Inc. Project: Reserve Turgyan Farms Client ID: B-2-5-1MSD	SDG No.: Q2818 Sample ID: Q2818-01 Percent Solids for Spike Sample: 87.5
--	---

Analyte	Units	Acceptance Limit	Sample Result	Conc. Qualifier	Duplicate Result	Conc. Qualifier	Dilution Factor	RPD/ AD	Qual	Analysis Date
Cyanide	mg/Kg	+/-20	2.40		2.50		1	4		08/11/2025

Duplicate Sample Summary

Client:	Earth Engineering Inc.	SDG No.:	Q2818
Project:	Reserve Turgyan Farms	Sample ID:	Q2888-01
Client ID:	VNJ-210DUP	Percent Solids for Spike Sample:	94.9

Analyte	Units	Acceptance Limit	Sample Result	Conc. Qualifier	Duplicate Result	Conc. Qualifier	Dilution Factor	RPD/ AD	Qual	Analysis Date
Hexavalent Chromium	mg/Kg	+/-20	0.073	U	0.072	U	1	0		08/19/2025

Laboratory Control Sample Summary

Client: Earth Engineering Inc.

SDG No.: Q2818

Project: Reserve Turgyan Farms

Run No.: LB136777

Analyte	Units	True Value	Result	Conc. Qualifier	% Recovery	Dilution Factor	Acceptance Limit %R	Analysis Date
Sample ID	PB169197BS							
Cyanide	mg/Kg	5	4.80		96	1	85-115	08/11/2025

Laboratory Control Sample Summary

Client: Earth Engineering Inc.

SDG No.: Q2818

Project: Reserve Turgyan Farms

Run No.: LB136872

Analyte	Units	True Value	Result	Conc. Qualifier	% Recovery	Dilution Factor	Acceptance Limit %R	Analysis Date
Sample ID	PB169305BS							
Hexavalent Chromium	mg/Kg	20	19.7		98	1	84-110	08/19/2025

Instrument ID: KONELAB

Daily Analysis Runlog For Sequence/QC Batch ID # LB136777

Review By	rubina	Review On	8/12/2025 8:10:38 AM
Supervise By	Sohil	Supervise On	8/12/2025 3:09:49 PM
SubDirectory	LB136777	Test	Cyanide
STD. NAME	STD REF.#		
ICAL Standard	WP114243,WP114244,WP114245,WP114246,WP114247,WP114248,WP114249		
ICV Standard	W3012		
CCV Standard	WP114244		
ICSA Standard	N/A		
CRI Standard	N/A		
LCS Standard	WP113838		
Chk Standard	WP112643,WP112900,WP114251		

Sr#	SampleId	ClientID	QcType	Date	Comment	Operator	Status
1	0.0PPBCN	0.0PPBCN	CAL1	08/11/25 10:04		rubina	OK
2	5.0PPBCN	5.0PPBCN	CAL2	08/11/25 10:04		rubina	OK
3	10PPBCN	10PPBCN	CAL3	08/11/25 10:04		rubina	OK
4	50PPBCN	50PPBCN	CAL4	08/11/25 10:04		rubina	OK
5	100PPBCN	100PPBCN	CAL5	08/11/25 10:04		rubina	OK
6	250PPBCN	250PPBCN	CAL6	08/11/25 10:04		rubina	OK
7	500PPBCN	500PPBCN	CAL7	08/11/25 10:04		rubina	OK
8	ICV1	ICV1	ICV	08/11/25 14:52		rubina	OK
9	ICB1	ICB1	ICB	08/11/25 14:53		rubina	OK
10	CCV1	CCV1	CCV	08/11/25 14:53		rubina	OK
11	CCB1	CCB1	CCB	08/11/25 14:53		rubina	OK
12	PB169197BL	PB169197BL	MB	08/11/25 14:53		rubina	OK
13	PB169197BS	PB169197BS	LCS	08/11/25 15:00		rubina	OK
14	Q2818-01	B-2-5-1	SAM	08/11/25 15:00		rubina	OK
15	Q2818-01DUP	B-2-5-1DUP	DUP	08/11/25 15:00		rubina	OK
16	Q2818-01MS	B-2-5-1MS	MS	08/11/25 15:00		rubina	OK
17	Q2818-01MSD	B-2-5-1MSD	MSD	08/11/25 15:00		rubina	OK
18	Q2818-02	B-3-5-2	SAM	08/11/25 15:05		rubina	OK

Instrument ID: KONELAB

Daily Analysis Runlog For Sequence/QC Batch ID # LB136777

Review By	rubina	Review On	8/12/2025 8:10:38 AM
Supervise By	Sohil	Supervise On	8/12/2025 3:09:49 PM
SubDirectory	LB136777	Test	Cyanide
STD. NAME	STD REF.#		
ICAL Standard	WP114243,WP114244,WP114245,WP114246,WP114247,WP114248,WP114249		
ICV Standard	W3012		
CCV Standard	WP114244		
ICSA Standard	N/A		
CRI Standard	N/A		
LCS Standard	WP113838		
Chk Standard	WP112643,WP112900,WP114251		

19	CCV2	CCV2	CCV	08/11/25 15:05		rubina	OK
20	CCB2	CCB2	CCB	08/11/25 15:05		rubina	OK

Instrument ID: SPECTROPHOTOMETER-1

Daily Analysis Runlog For Sequence/QC Batch ID # LB136872

Review By	Eman	Review On	8/19/2025 1:19:09 PM
Supervise By	jignesh	Supervise On	8/19/2025 2:51:17 PM
SubDirectory	LB136872	Test	Hexavalent Chromium
STD. NAME	STD REF.#		
ICAL Standard	N/A		
ICV Standard	N/A		
CCV Standard	N/A		
ICSA Standard	N/A		
CRI Standard	N/A		
LCS Standard	N/A		
Chk Standard	WP112831,WP112830,WP114312,WP114310,WP114313		

Sr#	SampleId	ClientID	QcType	Date	Comment	Operator	Status
1	CAL1	CAL1	CAL	08/19/25 12:30		Eman	OK
2	CAL2	CAL2	CAL	08/19/25 12:31		Eman	OK
3	CAL3	CAL3	CAL	08/19/25 12:32		Eman	OK
4	CAL4	CAL4	CAL	08/19/25 12:33		Eman	OK
5	CAL5	CAL5	CAL	08/19/25 12:34		Eman	OK
6	CAL6	CAL6	CAL	08/19/25 12:35		Eman	OK
7	CAL7	CAL7	CAL	08/19/25 12:36		Eman	OK
8	ICV	ICV	ICV	08/19/25 12:37		Eman	OK
9	ICB	ICB	ICB	08/19/25 12:38		Eman	OK
10	CCV1	CCV1	CCV	08/19/25 12:39		Eman	OK
11	CCB1	CCB1	CCB	08/19/25 12:40		Eman	OK
12	RL Check	RL Check	RL	08/19/25 12:41		Eman	OK
13	PB169305BL	PB169305BL	MB	08/19/25 12:42		Eman	OK
14	PB169305BS	PB169305BS	LCS	08/19/25 12:43		Eman	OK
15	Q2818-01	B-2-5-1	SAM	08/19/25 12:44		Eman	OK
16	Q2818-02	B-3-5-2	SAM	08/19/25 12:45		Eman	OK
17	Q2888-01	VNJ-210	SAM	08/19/25 12:46		Eman	OK
18	Q2888-01DUP	VNJ-210DUP	DUP	08/19/25 12:47		Eman	OK

Instrument ID: SPECTROPHOTOMETER-1

Daily Analysis Runlog For Sequence/QC Batch ID # LB136872

Review By	Eman	Review On	8/19/2025 1:19:09 PM
Supervise By	jignesh	Supervise On	8/19/2025 2:51:17 PM
SubDirectory	LB136872	Test	Hexavalent Chromium
STD. NAME	STD REF.#		
ICAL Standard	N/A		
ICV Standard	N/A		
CCV Standard	N/A		
ICSA Standard	N/A		
CRI Standard	N/A		
LCS Standard	N/A		
Chk Standard	WP112831,WP112830,WP114312,WP114310,WP114313		

19	Q2888-01MSPre	VNJ-210MS	MS	08/19/25 12:48		Eman	OK
20	Q2888-01MS2Ins	VNJ-210MS	MS	08/19/25 12:49		Eman	OK
21	Q2888-01MS3Post	VNJ-210MS	MS	08/19/25 12:50		Eman	OK
22	Q2893-01	LOD-MDL-SOIL-01-Q	SAM	08/19/25 12:51		Eman	OK
23	CCV2	CCV2	CCV	08/19/25 12:52		Eman	OK
24	CCB2	CCB2	CCB	08/19/25 12:53		Eman	OK
25	Q2893-02	LOQ-SOIL-02-QT3-20	SAM	08/19/25 12:54		Eman	OK
26	CCV3	CCV3	CCV	08/19/25 12:55		Eman	OK
27	CCB3	CCB3	CCB	08/19/25 12:56		Eman	OK

LAB CHRONICLE

OrderID:	Q2818	OrderDate:	8/11/2025 11:57:00 AM
Client:	Earth Engineering Inc.	Project:	Reserve Turgyan Farms
Contact:	Frank Dougherty, LSRP	Location:	J21

LabID	ClientID	Matrix	Test	Method	Sample Date	Prep Date	Anal Date	Received
Q2818-01	B-2-5-1	SOIL			08/11/25 08:50			08/11/25
			Cyanide	9012B		08/11/25	08/11/25 15:00	
			Hexavalent Chromium	7196A		08/19/25	08/19/25 12:44	
Q2818-02	B-3-5-2	SOIL			08/11/25 09:35			08/11/25
			Cyanide	9012B		08/11/25	08/11/25 15:05	
			Hexavalent Chromium	7196A		08/19/25	08/19/25 12:45	

SOP ID : M9012B-Total, Amenable and Reactive Cyanide-21

SDG No : N/A

Start Digest Date: 08/11/2025 Time : 12:45 Temp : 123 °C

Matrix : SOIL

End Digest Date: 08/11/2025 Time : 14:15 Temp : 126 °C

Pipette ID : WC

Balance ID : WC SC-7

Hood ID : HOOD#1

Digestion tube ID : M5595

Block Thermometer ID : WC CYANIDE

Block ID : MC-1

Filter paper ID : N/A

Prep Technician Signature: *[Signature]*

Weigh By : JP

pH Meter ID : N/A

Supervisor Signature: *[Signature]*

Standardized Name	MLS USED	STD REF. # FROM LOG
LCSS	1.0ML	WP113838
MS/MSD SPIKE SOL.	0.40ML	WP113837
PBS003	50.0ML	W3112
N/A	N/A	N/A
N/A	N/A	N/A

Chemical Used	ML/SAMPLE USED	Lot Number
0.25N NaOH	50.0ML	WP113836
50% v/v H2SO4	5.0ML	WP112826
51% w/v MgCL2	2.0ML	WP112827
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A

LAB SAMPLE ID	CLIENT SAMPLE ID	Wt(g)/Vol(ml)	Comment
S0	S0	N/A	N/A
S5.0	S5.0	N/A	N/A
S10.0	S10.0	N/A	N/A
S100.0	S100.0	N/A	N/A
S250.0	S250.0	N/A	N/A
S500.0	S500.0	N/A	N/A
ICV	ICV	N/A	AS PER PB169168
ICB	ICB	N/A	N/A
CCV	CCV	N/A	N/A
CCB	CCB	N/A	N/A
Midrange	Midrange	N/A	N/A
HIGHSTD	HIGHSTD	N/A	AS PER PB169168
LOWSTD	LOWSTD	N/A	AS PER PB169168

Extraction Conformance/Non-Conformance Comments:

N/A

Date / Time	Prepped Sample Relinquished By/Location	Received By/Location
08/11/2025 14:25	<i>[Signature]</i> / WC	RM (WC)
	Preparation Group	Analysis Group

Lab Sample ID	Client Sample ID	Initial Weight (g)	Final Vol (ml)	pH	Sulfide	Oxidizing	Nitrate/ Nitrite	Comment	Prep Pos
PB169197BL	PBS197	1.00	50	N/A	N/A	N/A	N/A	N/A	N/A
PB169197BS	LCS197	1.00	50	N/A	N/A	N/A	N/A	N/A	N/A
Q2818-01DUP	B-2-5-1DUP	1.02	50	N/A	N/A	N/A	N/A	N/A	N/A
Q2818-01MS	B-2-5-1MS	1.02	50	N/A	N/A	N/A	N/A	N/A	N/A
Q2818-01MSD	B-2-5-1MSD	1.01	50	N/A	N/A	N/A	N/A	N/A	N/A
Q2818-01	B-2-5-1	1.01	50	N/A	N/A	N/A	N/A	N/A	N/A
Q2818-02	B-3-5-2	1.04	50	N/A	N/A	N/A	N/A	N/A	N/A

SOP ID : M3060A,7196A-Hex.Chromium-27

SDG No : N/A

Matrix : SOIL

Pipette ID : WC

Balance ID : WC SC-7

Hood ID : HOOD#3

Block ID : WC S-2, WC S-1

Weigh By : RM

Start Digest Date: 08/19/2025 Time : 09:00 Temp : 90 °C

End Digest Date: 08/19/2025 Time : 10:00 Temp : 95 °C

if beleh 08/19/2025 10:30 90 °C
08/19/2025 11:30 94 °C

Digestion tube ID : M6054

Block Thermometer ID : WC-Block#1

Filter paper ID : 400213

Prep Technician Signature: *RM*

pH Meter ID : WC pH meter-1

Supervisor Signature: *JB*

Standard Name	MLS USED	STD REF. # FROM LOG
PRE-DIGESTION SPIKE	2.0ML	WP113880
INSOLUBLE SPIKE	0.02GM	W2202
POST-DIGESTION SPIKE	2.0ML	WP113880
LCSS	1.0ML	WP113881
PBS003	50.ML	W3112

Chemical Used	ML/SAMPLE USED	Lot Number
MAGNESIUM CHLORIDE	0.4GM	W3152
PHOSPHATE BUFFER	0.5ML	WP112903
HEX. DIGESTION SOLN.	50.0ML	WP114057
5M HNO3	5-7ML	WP112830
5N H2SO4	1-3ML	WP112831
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A
N/A	N/A	N/A

LAB SAMPLE ID	CLIENT SAMPLE ID	Vol(ml)	Comment
CAL1	CAL1	2.5ML	W3112
CAL2	CAL2	0.2ML	WP114309
CAL3	CAL3	0.5ML	WP114309
CAL4	CAL4	1ML	WP114309
CAL5	CAL5	0.2ML	WP113880
CAL6	CAL6	1ML	WP113880
CAL7	CAL7	2.0ML	WP113880
ICV	ICV	1ML	WP113881
ICB	ICB	2.5ML	W3112
CCV	CCV	1ML	WP113880
CCB	CCB	2.5ML	W3112

Extraction Conformance/Non-Conformance Comments:

08/19/2025 *RM*

N/A

Date / Time	Prepped Sample Relinquished By/Location	Received By/Location
	Preparation Group	Analysis Group

Lab Sample ID	Client Sample ID	Initial Weight (g)	Final Vol (ml)	pH	Sulfide	Oxidizing	Nitrate/ Nitrite	Comment	Prep Pos
PB169305BL	PBS305	2.50	100	N/A	N/A	N/A	N/A	N/A	N/A
PB169305BS	LCS305	2.50	100	N/A	N/A	N/A	N/A	N/A	N/A
Q2818-01	B-2-5-1	2.52	100	N/A	N/A	N/A	N/A	N/A	N/A
Q2818-02	B-3-5-2	2.51	100	N/A	N/A	N/A	N/A	N/A	N/A
Q2888-01	VNJ-210	2.54	100	N/A	N/A	N/A	N/A	N/A	N/A
Q2888-01DUP	VNJ-210DUP	2.57	100	N/A	N/A	N/A	N/A	N/A	N/A
Q2888-01MSPre	VNJ-210MSPRE	2.55	100	N/A	N/A	N/A	N/A	N/A	N/A
Q2888-01MS2Ins	VNJ-210MS2INS	2.53	100	N/A	N/A	N/A	N/A	N/A	N/A
Q2888-01MS3Post	VNJ-210MS3POST	2.57	100	N/A	N/A	N/A	N/A	N/A	N/A
Q2893-01	LOD-MDL-SOIL-01-QT3-2025	2.50	100	N/A	N/A	N/A	N/A	N/A	N/A
Q2893-02	LOQ-SOIL-02-QT3-2025	2.50	100	N/A	N/A	N/A	N/A	N/A	N/A