

Hit Summary Sheet
SW-846

SDG No.: Q3150 **Order ID:** Q3150
Client: Scalamandre – Tully JV **Project ID:** NYC DOT Harper Street Yard North

Sample ID	Client ID	Matrix	Parameter	Concentration	C	MDL	RDL	Units
Client ID : MER Rd Con Ed								
Q3150-06	MER Rd Con Ed	SOIL	Arsenic	7.55		0.19	1.02	mg/Kg
Q3150-06	MER Rd Con Ed	SOIL	Barium	66.8		0.75	5.11	mg/Kg
Q3150-06	MER Rd Con Ed	SOIL	Cadmium	0.60		0.025	0.31	mg/Kg
Q3150-06	MER Rd Con Ed	SOIL	Chromium	4.76		0.048	0.51	mg/Kg
Q3150-06	MER Rd Con Ed	SOIL	Lead	102		0.13	0.61	mg/Kg
Q3150-06	MER Rd Con Ed	SOIL	Mercury	0.026		0.0080	0.014	mg/Kg
Q3150-06	MER Rd Con Ed	SOIL	Silver	14.1		0.12	0.51	mg/Kg
Client ID : Mid Site Grid 5-7								
Q3150-07	Mid Site Grid 5-7	SOIL	Arsenic	14.5		0.23	1.21	mg/Kg
Q3150-07	Mid Site Grid 5-7	SOIL	Barium	77.7		0.88	6.04	mg/Kg
Q3150-07	Mid Site Grid 5-7	SOIL	Cadmium	0.65		0.029	0.36	mg/Kg
Q3150-07	Mid Site Grid 5-7	SOIL	Chromium	46.6		0.057	0.60	mg/Kg
Q3150-07	Mid Site Grid 5-7	SOIL	Lead	137		0.16	0.72	mg/Kg
Q3150-07	Mid Site Grid 5-7	SOIL	Mercury	0.22		0.0090	0.017	mg/Kg
Q3150-07	Mid Site Grid 5-7	SOIL	Selenium	0.81	J	0.31	1.21	mg/Kg



SAMPLE DATA

A

B

C

D

Report of Analysis

Client: Scalamandre – Tully JV
Project: NYC DOT Harper Street Yard North
Client Sample ID: MER Rd Con Ed
Lab Sample ID: Q3150-06
Level (low/med): low

Date Collected: 09/18/25
Date Received: 09/19/25
SDG No.: Q3150
Matrix: SOIL
% Solid: 90.6

Cas	Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units	Prep Date	Date Ana.	Ana Met.	Prep Met.
7440-38-2	Arsenic	7.55		1	0.19	1.02	mg/Kg	10/15/25 10:45	10/15/25 18:05	6010D	SW3050
7440-39-3	Barium	66.8	N	1	0.75	5.11	mg/Kg	10/15/25 10:45	10/15/25 18:05	6010D	SW3050
7440-43-9	Cadmium	0.60		1	0.025	0.31	mg/Kg	10/15/25 10:45	10/15/25 18:05	6010D	SW3050
7440-47-3	Chromium	4.76		1	0.048	0.51	mg/Kg	10/15/25 10:45	10/15/25 18:05	6010D	SW3050
7439-92-1	Lead	102		1	0.13	0.61	mg/Kg	10/15/25 10:45	10/15/25 18:05	6010D	SW3050
7439-97-6	Mercury	0.026		1	0.0080	0.014	mg/Kg	10/15/25 10:30	10/16/25 09:58	7471B	
7782-49-2	Selenium	0.27	U	1	0.27	1.02	mg/Kg	10/15/25 10:45	10/15/25 18:05	6010D	SW3050
7440-22-4	Silver	14.1	N	1	0.12	0.51	mg/Kg	10/15/25 10:45	10/15/25 18:05	6010D	SW3050

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

D = Dilution

Q = indicates LCS control criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

* = indicates the duplicate analysis is not within control limits.

E = Indicates the reported value is estimated because of the presence of interference.

OR = Over Range

N = Spiked sample recovery not within control limits

Report of Analysis

Client: Scalamandre – Tully JV
Project: NYC DOT Harper Street Yard North
Client Sample ID: Mid Site Grid 5-7
Lab Sample ID: Q3150-07
Level (low/med): low

Date Collected: 09/18/25
Date Received: 09/19/25
SDG No.: Q3150
Matrix: SOIL
% Solid: 76.7

Cas	Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units	Prep Date	Date Ana.	Ana Met.	Prep Met.
7440-38-2	Arsenic	14.5		1	0.23	1.21	mg/Kg	10/15/25 10:45	10/15/25 18:18	6010D	SW3050
7440-39-3	Barium	77.7	N	1	0.88	6.04	mg/Kg	10/15/25 10:45	10/15/25 18:18	6010D	SW3050
7440-43-9	Cadmium	0.65		1	0.029	0.36	mg/Kg	10/15/25 10:45	10/15/25 18:18	6010D	SW3050
7440-47-3	Chromium	46.6		1	0.057	0.60	mg/Kg	10/15/25 10:45	10/15/25 18:18	6010D	SW3050
7439-92-1	Lead	137		1	0.16	0.72	mg/Kg	10/15/25 10:45	10/15/25 18:18	6010D	SW3050
7439-97-6	Mercury	0.22		1	0.0090	0.017	mg/Kg	10/15/25 10:30	10/16/25 10:01	7471B	
7782-49-2	Selenium	0.81	J	1	0.31	1.21	mg/Kg	10/15/25 10:45	10/15/25 18:18	6010D	SW3050
7440-22-4	Silver	0.14	UN	1	0.14	0.60	mg/Kg	10/15/25 10:45	10/15/25 18:18	6010D	SW3050

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

D = Dilution

Q = indicates LCS control criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

* = indicates the duplicate analysis is not within control limits.

E = Indicates the reported value is estimated because of the presence of interference.

OR = Over Range

N = Spiked sample recovery not within control limits

LAB CHRONICLE

OrderID:	Q3150	OrderDate:	9/19/2025 11:55:00 AM
Client:	Scalamandre – Tully JV	Project:	NYC DOT Harper Street Yard North
Contact:	Dean Devoe	Location:	J23,VOA Lab

LabID	ClientID	Matrix	Test	Method	Sample Date	Prep Date	Anal Date	Received
Q3150-01	MER Rd Con Ed	TCLP	TCLP ICP Metals	6010D	09/18/25	09/22/25	09/22/25	09/19/25
			TCLP Mercury	7470A		09/22/25	09/23/25	
Q3150-03	Mid Site Grid 5-7	TCLP	TCLP ICP Metals	6010D	09/18/25	09/22/25	09/22/25	09/19/25
			TCLP Mercury	7470A		09/22/25	09/23/25	
Q3150-06	MER Rd Con Ed	SOIL	Mercury	7471B	09/18/25	10/15/25	10/16/25	09/19/25
			Metals ICP-RCRA	6010D		10/15/25	10/15/25	
Q3150-07	Mid Site Grid 5-7	SOIL	Mercury	7471B	09/18/25	10/15/25	10/16/25	09/19/25
			Metals ICP-RCRA	6010D		10/15/25	10/15/25	