

Report of Analysis

Client:	Sciacca General Contractors, LLC	Date Collected:	09/25/25
Project:	507 Franklin Ave Nutley	Date Received:	09/25/25
Client Sample ID:	WASTE	SDG No.:	Q3215
Lab Sample ID:	Q3215-01	Matrix:	SOIL
Level (low/med):	low	% Solid:	90.5

Cas	Parameter	Conc.	Qua.	DF	MDL	LOQ / CRQL	Units(Dry Weight)	Prep Date	Date Ana.	Ana Met.	Prep Met.
7440-38-2	Arsenic	3.15		1	0.19	1.00	mg/Kg	09/29/25 10:20	09/30/25 17:23	6010D	SW3050
7440-39-3	Barium	80.2	*	1	0.73	4.98	mg/Kg	09/29/25 10:20	09/30/25 17:23	6010D	SW3050
7440-43-9	Cadmium	0.024	UN	1	0.024	0.30	mg/Kg	09/29/25 10:20	09/30/25 17:23	6010D	SW3050
7440-47-3	Chromium	14.3		1	0.047	0.50	mg/Kg	09/29/25 10:20	09/30/25 17:23	6010D	SW3050
7439-92-1	Lead	83.6	*	1	0.13	0.60	mg/Kg	09/29/25 10:20	09/30/25 17:23	6010D	SW3050
7439-97-6	Mercury	0.073		1	0.0080	0.014	mg/Kg	09/29/25 16:00	09/30/25 10:07	7471B	
7782-49-2	Selenium	0.45	J	1	0.26	1.00	mg/Kg	09/29/25 10:20	09/30/25 17:23	6010D	SW3050
7440-22-4	Silver	0.12	U	1	0.12	0.50	mg/Kg	09/29/25 10:20	09/30/25 17:23	6010D	SW3050

Color Before:	Brown	Clarity Before:	Texture:	Medium
Color After:	Yellow	Clarity After:	Artifacts:	No
Comments:	METALS RCRA			

U = Not Detected
 LOQ = Limit of Quantitation
 MDL = Method Detection Limit
 LOD = Limit of Detection
 D = Dilution
 Q = indicates LCS control criteria did not meet requirements

J = Estimated Value
 B = Analyte Found in Associated Method Blank
 * = indicates the duplicate analysis is not within control limits.
 E = Indicates the reported value is estimated because of the presence of interference.
 OR = Over Range
 N = Spiked sample recovery not within control limits