

Report of Analysis

Client:	Sciacca General Contractors, LLC		Date Collected:	09/25/25	
Project:	507 Franklin Ave Nutley		Date Received:	09/25/25	
Client Sample ID:	WASTE		SDG No.:	Q3215	
Lab Sample ID:	Q3215-01		Matrix:	SOIL	
Analytical Method:	8260D		% Solid:	90.5	
Sample Wt/Vol:	5	Units: g	Final Vol:	5000	uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10	
GC Column:	RXI-624	ID : 0.25	Level :	LOW	
Prep Method :					

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VW032280.D	1	09/26/25 15:09	vw092625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
TARGETS						
75-71-8	Dichlorodifluoromethane	1.30	U	1.30	5.50	ug/Kg
74-87-3	Chloromethane	1.30	U	1.30	5.50	ug/Kg
75-01-4	Vinyl Chloride	0.87	U	0.87	5.50	ug/Kg
74-83-9	Bromomethane	1.20	U	1.20	5.50	ug/Kg
75-00-3	Chloroethane	1.40	U	1.40	5.50	ug/Kg
75-69-4	Trichlorofluoromethane	1.30	U	1.30	5.50	ug/Kg
76-13-1	1,1,2-Trichlorotrifluoroethane	1.20	U	1.20	5.50	ug/Kg
75-35-4	1,1-Dichloroethene	1.10	U	1.10	5.50	ug/Kg
67-64-1	Acetone	5.20	U	5.20	27.6	ug/Kg
75-15-0	Carbon Disulfide	1.20	U	1.20	5.50	ug/Kg
1634-04-4	Methyl tert-butyl Ether	0.81	U	0.81	5.50	ug/Kg
79-20-9	Methyl Acetate	1.70	U	1.70	5.50	ug/Kg
75-09-2	Methylene Chloride	3.90	U	3.90	11.0	ug/Kg
156-60-5	trans-1,2-Dichloroethene	0.95	U	0.95	5.50	ug/Kg
75-34-3	1,1-Dichloroethane	0.88	U	0.88	5.50	ug/Kg
110-82-7	Cyclohexane	0.87	U	0.87	5.50	ug/Kg
78-93-3	2-Butanone	7.20	U	7.20	27.6	ug/Kg
56-23-5	Carbon Tetrachloride	1.10	U	1.10	5.50	ug/Kg
156-59-2	cis-1,2-Dichloroethene	0.83	U	0.83	5.50	ug/Kg
74-97-5	Bromochloromethane	1.30	U	1.30	5.50	ug/Kg
67-66-3	Chloroform	0.93	U	0.93	5.50	ug/Kg
71-55-6	1,1,1-Trichloroethane	1.00	U	1.00	5.50	ug/Kg
108-87-2	Methylcyclohexane	1.00	U	1.00	5.50	ug/Kg
71-43-2	Benzene	0.87	U	0.87	5.50	ug/Kg
107-06-2	1,2-Dichloroethane	0.87	U	0.87	5.50	ug/Kg
79-01-6	Trichloroethene	0.90	U	0.90	5.50	ug/Kg
78-87-5	1,2-Dichloropropane	1.00	U	1.00	5.50	ug/Kg
75-27-4	Bromodichloromethane	0.86	U	0.86	5.50	ug/Kg
108-10-1	4-Methyl-2-Pentanone	4.00	U	4.00	27.6	ug/Kg
108-88-3	Toluene	0.86	U	0.86	5.50	ug/Kg

Report of Analysis

Client:	Sciacca General Contractors, LLC	Date Collected:	09/25/25
Project:	507 Franklin Ave Nutley	Date Received:	09/25/25
Client Sample ID:	WASTE	SDG No.:	Q3215
Lab Sample ID:	Q3215-01	Matrix:	SOIL
Analytical Method:	8260D	% Solid:	90.5
Sample Wt/Vol:	5	Units:	g
Soil Aliquot Vol:			uL
GC Column:	RXI-624	ID :	0.25
Prep Method :		Level :	LOW

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VW032280.D	1	09/26/25 15:09	vw092625

[illegible]

Report of Analysis

Client:	Sciacca General Contractors, LLC		Date Collected:	09/25/25	
Project:	507 Franklin Ave Nutley		Date Received:	09/25/25	
Client Sample ID:	WASTE		SDG No.:	Q3215	
Lab Sample ID:	Q3215-01		Matrix:	SOIL	
Analytical Method:	8260D		% Solid:	90.5	
Sample Wt/Vol:	5	Units: g	Final Vol:	5000	uL
Soil Aliquot Vol:		uL	Test:	VOC-TCLVOA-10	
GC Column:	RXI-624	ID : 0.25	Level :	LOW	
Prep Method :					

File ID/Qc Batch:	Dilution:	Date Analyzed	Prep Batch ID
VW032280.D	1	09/26/25 15:09	vw092625

CAS Number	Parameter	Conc.	Qualifier	MDL	LOQ / CRQL	Units(Dry Weight)
000110-54-3	n-Hexane	6.40	J		5.97	ug/Kg

U = Not Detected

LOQ = Limit of Quantitation

MDL = Method Detection Limit

LOD = Limit of Detection

E = Value Exceeds Calibration Range

Q = indicates LCS control criteria did not meet requirements

M = MS/MSD acceptance criteria did not meet requirements

J = Estimated Value

B = Analyte Found in Associated Method Blank

N = Presumptive Evidence of a Compound

* = Values outside of QC limits

D = Dilution

() = Laboratory InHouse Limit

A = Aldol-Condensation Reaction Products